70656

SUMMARY OF QUANTITIES

LOCATION OF WORK:

U.S. 36 & U.S. 150 / IL 1

Edgar County Highway Lighting 100% State

CONSTRUCTION TYPE CODE:

Y030-1E

CODE NO	ITEM	UNIT	TOTAL QUANTITY
67100100	MOBILIZATION	L SUM	1.0
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1.0
80400100	ELECTRIC SERVICE INSTALLATION	EACH	1.0
81020500	CONDUIT PUSHED, 2" DIA., INTERMEDIATE METAL	FOOT	270.0
81603000	UNIT DUCT, 600V, 2-1C NO.8, 1/C NO.8 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE	FOOT	544.0
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	244.0
82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	4.0
83002500	LIGHT POLE, ALUMINUM, 40 FT. M.H., 12 FT. DAVIT ARM	EACH	4.0
83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	24.0
83800505 \$4200500 84200600	BREAKAWAY DEVICE, COUPLING, WITH ALUMINUM SKIRT REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE REMOVAL OF EXISTING LIGHTING UNIT, NO SALVAGE	EACH EACH EACH	16.0 2.0 10.0
84200800	POLE FOUNDATION, REMOVED	EACH	12.0
84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	1.0
84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	1.0
X8250207	LIGHTING CONTROLLER PHOTOCELL RELAY, SPECIAL	EACH	1.0

	İ									
	FILE NAME =	USER NAME = coll:erb+	DESIGNED -	REVISED -			F.A.P. SECT	TION C	OUNTY TO	TOTAL SHEET
	c:\projects\d502807 (v8)\4735\plan.dgn		DRAWN ~	REVISED -	STATE OF ILLINOIS	SUMMARY OF QUANTITIES	323 14	igi F	FOCAR	Q 3
İ		PLOT SCALE = 40.0000 '/ IN.	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION		1 262 1 143	CO	ONTRACT N	NO. 70656
		PLOT DATE = 10/24/2007	DATE -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.	FEO. ROAD DIST. NO.	ILLINOIS FED. AID PRO.		