
STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION



Contract No. 98821

NOTES

Bar splicer assemblies shall be of an approved type and shall develop in tension at least 125 percent of the yield strength of the lapped reinforcement bars.

Splicer rods shall be of minimum 60 ksi yield strength, threaded or coiled full length. All reinforcement bars shall be lapped and tied to the splicer rods or dowel bars. Bar splicer assemblies shall be epoxy coated according to the requirements for reinforcement bars.

Other systems of similar design may be submitted to the Engineer for approval. Approval shall be based on certified test results from an approved testing laboratory that the proposed bar splicer assembly satisfies the following requirements:


Minimum Capacity (Tension in kips) = $1.25 \times fy \times A_t$

(Tension III Kips)

Minimum *Pull-out Strength = $0.66 \times fy \times A_t$

Where fy = Yield strength of lapped reinforcement bars in ksi. A_t = Tensile stress area of lapped reinforcement bars. * = 28 day concrete

BAR SPLICER ASSEMBLIES				
Bar Size to be Spliced	Splicer Rod or Dowel Bar Length	Strength Requirements		
		Min. Capacity kips - tension	Min. Pull-Out Strength kips - tension	
#4	1'-8''	14.7	7.9	
#5	2'-0"	23.0	12.3	
#6	2'-7''	33.1	17.4	
#7	3′-5″	45.1	23.8	
#8	4'-6''	58.9	31.3	
#9	5′-9″	75,0	39.6	
#10	7′-3′′	95.0	50.3	
#11	9′-0′′	117.4	61.8	



BAR SPLICER ASSEMBLY ALTERNATIVES

WELDED SECTIONS

ROLLED THREAD DOWEL BAR

** ONE PIECE

-Wire Connector

The diameter of this part is


equal or larger than the

diameter of bar spliced.

** Heavy Hex Nuts conforming to ASTM A 563, Grade C, D or DH may be used.

INSTALLATION AND SETTING METHODS

"A": Set bar splicer assembly by means of a template bolt. "B": Set bar splicer assembly by nailing to wood forms or cementing to steel forms. (E): Indicates epoxy coating.



FOR INTEGRAL OR SEMI-INTEGRAL ABUTMENTS

Bar Splicer for #5 bar Min. Capacity = 23.0 kips - tension Min. Pull-out Strength = 12.3 kips - tension No. Required = 72


DESIGNED Dewey H. Coultas Ray Ahanchi DRAWN DHC/GRA CHECKED


11-1-06

The diameter of this part

of the bar spliced.

is the same as the diameter





Bar Size	No. Assemblies Required	Location

BAR SPLICER ASSEMBLY DETAILS F.A.P. RTE. 869 - SEC. (101VB)B-1 FRANKLIN COUNTY STATION 177+17.38 STRUCTURE NO. 028-0077

BSD-1