


## STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION




SECTION G-G







## EXPANSION JOINT DETAIL (in Parapet)



(in Parapet)



EXPANSION JOINT SEALING DETAIL



**EXPANSION JOINT** 

COOK	460	341
STA.		
S FED. AID	PROJECT	
		S FED. AID PROJECT

BILL OF	MATERIAL
---------	----------

BILL OF MATENTAL					
Bar	No.	Size	Length	Shape	
d1(E)	41	#5	4'-3"		
d2(E)	42	#7	5′-8"		
<i>((</i> , )			407.00		
e1(E)	7	#4	19'-8"		
e2(E)	7	#4	20'-7"		
e3(E)	14	#4	21'-10"		
·					
Item		Unit	Quantity		
Concrete Removal			Cu Yd	3.2	
Concrete Superstructure			Cu Yd	8.5	
Protective Coat			Sq Yd	39	
Reinforcement Bars, Epoxy Coated			Pound	1070	
Chain Link Fence, 42" Attached to Structure (Special)			Foot	41	
Rustication Finish			Sq Ft	74.	
Porous Granular Embankment			Cu Yd	5	
Structure Excavation		Cu Yd	6		
			-		

## NOTES:

1. Work Sheets CGc1 thru CGc3 together.

CGc3 OF 3

REVISIONS
NAME
DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)

SECTIONS, DETAILS & BILL OF MATERIAL
SOUTHEAST CORNER GARDEN
SOUTH WENTWORTH AVE. AT WEST 63rd STREET
SECTION 2021-922 PT.1-AC
STATION 103+65.74 TO 104+00.81
COOK COUNTY

SCALE: None
DATE: October 29, 2004
CHECKED BY: DC

CTE ENGINEERS

CONSOBR TOWNSEND BEMRODYNE ENGINEERS, INC.
303 EAST MACKER DRIVE, SUITE 600
CHICAGO LILHIOIS 6000-1222, PHOME (3/2) 938-0300