INDEX OF SHEETS

STATE STANDARDS

1	TITLE SHEET	701011 - 02	OFF-ROAD MOVING OPERATIONS, 2L, 2W, DAY ONLY
2	INDEX OF SHEETS, STATE STANDARDS, AND GENERAL NOTES	701101 - <i>0</i>2	OFF-ROAD OPERATIONS MULTILANE, 4.5 m (15') TO
3	SUMMARY OF QUANTITIES		600 mm (24") FROM PAVEMENT EDGE
4	LOCATION MAP	701901 -0	TRAFFIC CONTROL DEVICES
5-8	STRUCTURAL REPAIRS LOC 1 (SN 016-1029)		
9-12	STRUCTURAL REPAIRS LOC 2 (SN 016-1030)		
13-15	STRUCTURAL REPAIRS LOC 3 (SN 016-2448)		

GENERAL NOTES

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT 800-892-0123 or 811 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS FACILITIES. (48 HOUR NOTIFICATION IS REQUIRED)

THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES, THE CITY OF CHICAGO.

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.

DO NOT SCALE PLANS FOR CONSTRUCTION DIMENSIONS

THE CONTRACTOR SHALL CONTACT THE DISTRICT ONE TRAFFIC CONTROL SUPERVISOR AT (847) 705-4151 FOR EXPRESSWAYS. A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINING OF WORK.

THESE PLANS HAVE BEEN PREPARED FROM NOTES RECIEVE FROM BRIDGE INSPECTIONS.

PLAN DIMESIONS AND DETAILS RELATIVE TO EXISTING PLANS ARE SUBJECT TO ROUTINE VARIATIONS THE CONTRACTOR SHALL FIELD VERIFY EXISTING DIMENSIONS AND DETAILS AFFECTIND NEW CONSTRUCTION AND MAKE NECESSARY APPROVED ADJUSTMENTS PRIOR TO CONSTRUCTION OR ORDERING OF MATERIALS. SUCH VARIATIONS SHALL NOT BE CAUSE FOR ADDITIONAL COMPENSATION FOR A CHANGE IN SCOPE OF THE WORK, HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY ACTUALLY FURNISED BASED UPON THE UNIT PRICE BID FOR THE WORK.

DELETED

27

38

16-19 STRUCTURAL REPAIRS LOC 4 (SN 016-2449)

20-26 STRUCTURAL REPAIRS LOC 5 (SN 016-2450)

28-34 STRUCTURAL REPAIRS LOC 7 (SN 016-2452)

35-37 STRUCTURAL REPAIRS LOC 8 (SN 016-2453)

STRUCTURAL REPAIRS LOC 6 (SN 016-2451)

TRAFFIC CONTROL FOR SHOULDER CLOSURES & PARTIAL RAMP CLOSURES (TC-17)

DESIGNED -REVISED FILE NAME = USER NAME = estimables DRAWN REVISED ::\pw_work\PWIDOT\ESTIMABLEK\dØ161538\D 81309-sht-plan.dgn REVISED CHECKED PLOT SCALE = 100.0000 '/ IN. PLOT DATE = 1/5/2010 DATE REVISED

STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION**

BRIDGE SUBSTRUCTURE REPAIR INDEX OF SHEET, STATE STANDARDS & GENERAL NOTES SHEET NO. OF SHEETS STA.

COUNTY TOTAL SHEET NO. SECTION COOK 39 2 CONTRACT NO. 60H77