

## NOTES:

- 1. USE BLACK LETTERING ON ORANGE BACKGROUND.
- 2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
- 3. ERECT SIGN (1) WITH INSTALLED PANEL (2) ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
- 4. REMOVE PANEL (2) SOON AFTER THE START OF CONSTRUCTION.
- 5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
- 6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
- 7. SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

		PLOT SCALE = 50.0000 '/ IN.	CHECKED -	REVISED -T. RAMMACHER 02-02-9	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INFORMATION SIGN		TC-22	CONTRACT I	NO. 60H	NO. 60H78
		PLOT DATE = 12/16/2009	DATE -	REVISED - C. JUCIUS 01-31-07	DEFAITMENT OF THANSFORTATION	SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.	FED. ROAD DIST.	NO. 1 ILLINOIS FED. A		NO. 60H	78