


Notes:

The exterior surfaces of the floor drains shall be painted with the finish coat as specified in the special provisions for Cleaning and Painting New Metal Structures. The exterior surfaces of the drains shall be cleaned according to Society of Protective Coatings Spec. SSPC-SP1 prior to painting.

Fiberglass pipe shall conform to ASTM D 2996, with short-time rupture strength hoop tensile stress of 30,000 p.s.i. minimum.



BAR s(E)


Notes:

Reinforcement bars in diaphragm are billed with superstructure on sheet S-7.


Concrete in diaphragm is included with Concrete Superstructure on sheet S-7.

The s(E) and $s_1(E)$ bars shall be placed parallel to the beams. Spacing for these bars shall be at right angles to the beams.

Epoxy grout d₅(E) bars in 6" (min.) drilled holes according to Section 584 of Standard Specification




STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION



$A \blacktriangleleft I$

DIAPHRAGM ELEVATION AT ABUTMENT



SECTION A-A

Dimensions at right angles to abutment, except as shown.

WHITEHALL AVENUE OVER
ADDISON CREEK
F.A. RTE. 4025
SECTION 09-00071-00-BR
COOK COUNTY
STATION 30+67.04
STRUCTURE No. 016-7618

SHEET NO.	
S-8	
SHEETS	

F.A. RTE.			SEC	TION			COUNTY	TOT SHEE	AL TS	SHEET NO.
4025	4025 09-00071-00-BR					COOK	31		20	
							CONTRACT	NO.	63	437
FED. RO	DAC	DIST.	NO.	ILLINOIS	FED.	AID	PROJECT			

DESIGNED -	
CHECKED -	EXAMINED
DRAWN -	PASSED ENGINEER OF BRIDGE DE
CHECKED -	ENGINEER OF BRIDGES AND STRUCTO