STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

2-#6 h₄ bars in

Top of Headwall


1'-0"

6'-0" typ.

4" typ.

30'-0"

— © Culvert



ELEVATION

--- Sta. 149+29.00

BAR V2 BAR d 10′-5"

8"

BARS h3 & h8

BAR hg



44'-6" Retention along North Proposed R.O.W. -Ground Surface / top Elev. 529.95

of soil retention system Exposed surface area - Maximum Elev. 525.70 excavation line

> TEMPORARY SOIL RETENTION SYSTEM DETAILS

36'-0"

-34" Drip Notch

SECTION THRU HEADWALL (Up Stream End Only)

Reinforcement bars shall conform to the requiremnets of ASTM A 706, Grade 60. See Special Provisions.

GENERAL NOTES

- 2. Layout of slope protection system may be varied in the field to suit ground conditions as directed by the Engineer.
- 3. The material used to replace the unsuitable material removed below the bottom of the proposed cast-in-place reinforced concrete box culvert and wingwalls shall be paid for as "Rock Fill".
- 4. Precast concrete culvert alternate will not be allowed.
- 5. A distance of half the wingwall length, but not less than six feet, of the barrel shall be poured monolithically with the wingwalls.
- 6. All construction joints shall be bonded.

BILL OF MATERIAL

Bar	No.	Size	Length	Shape
a ₁	238	#8	14'-8"	
<i>a</i> ₂	36	#4	12′-3"	
d	13	#4	4'-6"	
h	30	#6	30′-11"	
h ₁	66	#5	23'-11"	
h ₂	28	#6	35'-3"	
h ₃	24	#7	8′-0"	
h ₄	4	#6	13′-0"	
h ₈	20	#7	14'-6"	/
hg .	16	#4	12'-1"	L
h10	2	#6	10′-5"	
h _{II}	8	#4	13'-1".	
h ₁₂	8	#6	13'-1"	
V	193	#4	8'-3"	
VI	8	#4	11'-1"	
V2	43	#4	9'-1"	
Z	8	#6	5′-6"	
Concrete Box Culverts			Cu. Yd. Pound	87.1
Reinfor	Reinforcement Bars			17,420

Bars indicated thus 7 x 2-#6 etc. indicates 7 lines of bars with 2 lengths

15

STRUCTURE DIMENSIONS, DETAILS AND GENERAL NOTES US ROUTE 6 OVER UNNAMED TRIBUTARY TO THE ILLINOIS RIVER STRUCTURE NO. 050-2643

TOTAL SHEET NO. SECTION COUNTY SHEET NO. 2 623 LASALLE 25 (H)I-1 OF 4 SHEETS CONTRACT NO. 66914 FED. ROAD DIST. NO. 1 | ILLINOIS FED. AID PROJECT

DESIGNED LM CHECKED GBC / SMK

Drop Structure Side Wall, typ.

10'-8" typ.

2-#6 h4 bars in

Top of Headwall

1'-0"

1" typ.

38'-8"

68′-8"

PLAN

DRAWN LM CHECKED GBC / SMK

Drop -Strucuture

End Wall

Delta Engineering, Inc.
CONSULTING ENGINEERS, CONSTRUCTION MANAGERS, SURVEYORS
161 W. JOSHON Blyd. Sufte 910 Chicogo. R. 60504-2001