DETECTABLE WARNINGS SCHEDULE									
STATION	SIDE	DETECTABLE WARNINGS (SQ FT)							
EXCHANGE AVE									
12+25.94	LT	10							
12+25.94	RT	10							
21+39.28	LT	10							
21+39.40	RT	10							
22+29.28	LT	10							
22+29.40	RT	10							
7TH STREET									
15+96.98	RT	10							
15+97.01	LT	10							
9TH STREET									
4+16.52	RT	. 10							
4+16.60	LT	10							
5+27.00	RT	10							
5+27.11	LT	10							
TOTAL		120							

					PATCHING SCHEDULE			
LOCATION	SIDE	SIZE			CLASS A PATCHES, TYPE IV	SAW CUTS	DOWEL BARS (EA)	TIE BARS
		FT	x	FT				(EA)
I-55 N								
79+98.00	LT	12.0	Х	68.0	91	104	20	67
79+98.00	RT	12.0	Х	68.0	91	104	. 20	67
	TOTALS				182	208	40	134

FENCE SCHEDULE									
LOCATION	WOVEN WIRE FENCE,4' (LF)								
RAMP 0									
15+58.44 TO 23+86.08	828								
TOTAL	828								

	FILE NAME =	USER NAME = \$USER\$	DESIGNED	-	RRV	REVISED	
# ₩ ₩	\$FILEL		DRAWN	-	JMC	REVISED	-
< □ ⊢		PLOT SCALE = \$SCALE\$	CHECKED	-	DRH	REVISED	-
⊕ ⊬		PLOT DATE = *DATE*	DATE	-	OCTOBER 15, 2009	REVISED	-

								F.A.I. SECTION		TOTAL	SHEET NO.
SCHEDULE OF QUANTITIES							70	82-2-1HB	ST. CLAIR	236	27
- AND THE STATE OF									CONTRACT	Γ NO. 7	76C55
SCALE:	SHEET NO.	7 OF	8	SHEETS	STA.	TO STA.	FED. ROAD	DIST. NO. ILLINOIS FED.	AID PROJECT		