

INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	SIGNATURE SHEET, INDEX OF SHEETS, STANDARDS, GENERAL NOTES, STRUCTURES WITHIN PROJECT, COMMITMENTS
3-4	SUMMARY OF QUANTITIES
5	TYPICAL SECTIONS
6-8	SCHEDULES
9-10	CULVERT DETAILS
11	DETOUR PLAN
12	DETAIL - PRECAST BOX CULVERT END SECTION
13	DETAIL - PRECAST BOX CULVERT SECTION (M259)
14	DETAIL - PAYMENT LIMITS FOR PRECAST CONCRETE BOX CULVERTS

GENERAL NOTES

FACTORS USED FOR ESTIMATING PLAN QUANTITIES ARE AS FOLLOWS AND SHALL NOT BE USED FOR THE BASIS OF FINAL QUANTITIES:

ALL HOT-MIX ASPHALT	2.016 TONS/CU. YD.
ALL AGGREGATE	2.05 TONS/CU. YD.
BITUMINOUS MATERIALS:	
ON PAVEMENT	0.09 GAL./SQ. YD.
ON AGGREGATE SURFACE	0.32 GAL./SQ. YD.
AGGREGATE (PRIME COAT)	0.0015 TONS/SQ. YD.
RIPRAP	1.50 TONS/CU. YD.

THE QUANTITY OF SHORT TERM PAVEMENT MARKING SHOWN IN THE PLANS IS BASED ON ONE APPLICATION.

ALL PAVEMENT MARKINGS SHALL BE LOCATED AND RECORDED BEFORE PAVEMENT REMOVAL.

PRIOR TO PLACEMENT OF THE FINAL PAVEMENT MARKINGS THE RESIDENT ENGINEER SHOULD CONTACT THE BUREAU OF OPERATIONS AND ARRANGE FOR INSPECTION AND APPROVAL OF THE PAVEMENT MARKING LAYOUT.

THERE ARE NO AVAILABLE WASTE SITES ON THE EXISTING RIGHT OF WAY WITHIN THE PROJECT LIMITS. DISPOSAL WILL BE THE RESPONSIBILITY OF THE CONTRACTOR AND WASTE MUST BE DISPOSED OF IN ACCORDANCE WITH ARTICLE 202.03 OF THE STANDARD SPECIFICATIONS.

STATIONING SHOWN IN THE SCHEDULES IS BASED ON STAMPED STATIONS IN THE EXISTING PAVEMENT AND FROM OLD PLANS. MINOR ADJUSTMENTS MAY BE REQUIRED AS DIRECTED BY THE ENGINEER.

PLAN DIMENSIONS AND DETAILS RELATIVE TO EXISTING PLANS ARE SUBJECT TO NOMINAL CONSTRUCTION VARIATIONS. THE CONTRACTOR SHALL FIELD VERIFY EXISTING DIMENSIONS AND DETAILS AFFECTING NEW CONSTRUCTION AND MAKE NECESSARY APPROVED ADJUSTMENTS PRIOR TO CONSTRUCTION OR ORDERING OF MATERIALS. SUCH VARIATIONS SHALL NOT BE CAUSE FOR ADDITIONAL COMPENSTATION FOR A CHANGE IN THE SCOPE OF THE WORK. HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY ACTUALLY FURNISHED AT THE UNIT PRICE BID FOR THE WORK.

ALL EARTH EXCAVATION SHALL BE INCLUDED IN THE COST OF PRECAST CONCRETE BOX CULVERT 4' X 3'.

STANDARDS

280001-04	701301-03
420001-07	701311-03
420101-04	701901-01
606201-02	780001-02
701001-02	BLR 17-4
701006-03	BLR 21-8
701201-03	

STRUCTURES WITHIN PROJECT LIMITS

STRUCTURE NO.	OPERATING RATING	INVENTORY RATING	POSTING	MTD APPROVAL
NONE				

COMMITMENTS

NONE

Prepared By:	<i>Dennis W. Hildebrand</i> DISTRICT STUDIES & PLANS ENGINEER
Examined By:	<i>Nancy Kis</i> DISTRICT LAND ACQUISITION ENGINEER
Examined By:	<i>Cassie Nelson</i> DISTRICT PROGRAM DEVELOPMENT ENGINEER
Examined By:	<i>Carl Wiley</i> DISTRICT OPERATIONS ENGINEER
Examined By:	<i>Jim Switzer</i> DISTRICT CONSTRUCTION ENGINEER
Examined By:	<i>Bryan Rebley</i> DISTRICT MATERIALS ENGINEER
Examined By:	<i>John Smith</i> DISTRICT PROJECT IMPLEMENTATION ENGINEER
Examined By:	<i>Sammy White</i> ASSISTANT REGIONAL ENGINEER
Approved By:	<i>Marg C. Sami</i> DEPUTY DIRECTOR OF HIGHWAYS, REGION 5 ENGINEER
DATE: <i>Dec 8th</i> 2009	

FILE NAME =	USER NAME = kranzjo	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS, STANDARDS GENERAL NOTES, SIGNATURES		F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ct:\pr-work\pwidot\KranzJC\0155533\78158	3-sh-t-pln.dgn	DRAWN -	REVISED -		SCALE:	SHEET NO. OF SHEETS	STA.	726	(1201)-1	PULASKI	14	2
	PLOT SCALE = 100.0000 "/ IN.	CHECKED -	REVISED -									
	PLOT DATE = 11/20/2009	DATE -	REVISED -									
							CONTRACT NO. 78158		ILLINOIS FED. AID PROJECT			