

PROPOSED SERVICE INSTALLATION POLE TOP MOUNTED TRANSFORMER

SER NAME = chartke DESIGNED - BDL REVISED SEC Group, Inc. REVISED DRAWN - CMH PLOT SCALE = NTS CHECKED - APS REVISED PLOT DATE = 1/16/2009 DATE 12/16/08 REVISED

VILLAGE OF NILES

SCALE: NTS

ELECTRICAL SERVICE INSTALLATION ABOVE GROUND 3513 SHEET NO. 10 OF 13 SHEETS STA.

COUNTY TOTAL SHEE SHEETS NO. SECTION 08-00107-01-PV COOK 169 83 CONTRACT NO.

NOTES:

- 1. THE PAY ITEM "ELECTRIC UTILITY SERVICE CONNECTION" SHALL CONSIST OF PAYMENT FOR WORK PERFORMED BY THE ELECTRIC UTILITY COMPANY IN PROVIDING OR MODIFYING FLECTRIC SERVICE AS INDICATED.
- 2. THE PAY ITEM— "ELECTRIC SERVICE INSTALLATION"
 SHALL CONSIST OF ALL MATERIAL AND LABOR REQUIRED
 TO EXTEND. CONNECT OR MODIFY THE ELECTRIC SERVICE AS INDICATED OR SPECIFIED, WHICH IS OVER AND ABOVE THE WORK PERFORMED BY UTILITY COMPANY. THE SERVICE METER SOCKET, AS APPLICABLE, MOUNTED ELSEWHERE, SHALL BE INCLUDED IN THIS PAY ITEM.
- 3. SERVICE VOLTAGE SHALL BE AS INDICATED ELSEWHERE IN THE PROJECT DRAWINGS.
- 4. ELECTRIC SERVICE SPAN BETWEEN THE CONTROLLER AND UTILITY TRANSFORMER SHALL NOT EXCEED 250 FEET.
- 5. CONDUIT FOR SERVICE CABLE:
- 5.1 CONDIUT DIAMETER AND CONDUIT FITTINGS SHALL BE SIZED WITH WIRE GAUGE AND MAXIMUM NUMBER OF CONDUCTORS PERMITTED BY NEC.
- 5.2 CONDUIT FOR SERVICE CABLE SHALL BE AS INDICATED AND SHALL BE MEASURED SEPARATELY FOR PAYMENT.
- 5.3 PVC COATED GALVANIZED STEEL CONDUIT AND CONDUIT FITTINGS OF THE SAME TYPE SHALL BE CAREFULLY INSTALLED WITH MANUFACTURER'S RECOMMENDED TOOLS AND PROCEDURES. DAMAGE TO CONDUIT SHALL BE REPAIRED WITH COMPATIBLE PVC TOUCH-UP MATERIAL TO THE SATISFACTION OF THE ENGINEER OR THE DAMAGED MATERIAL SHALL BE REPLACED AT NO ADDITIONAL COST.
- 5.4 THE COUPLING (CONDUIT FITTING) SHALL BE A METALIC TO NON-METALIC ADAPTER BETWEEN STEEL CONDUIT AND PVC CONDUIT.
- 5.5 CONCRETE COVER OVER THE ENCASED RAGEWAY RUN SHALL BE A MINIMUM 3 INCH ALL AROUND.
- 6. PLANS AND DETAILS INDICATE THE GENERAL NATURE AND REQUIREMENTS OF THE UTILITY SERVICE WITHOUT EVERY ACCESSORY AND ATTACHMENT THE CONTRACTOR IS DBLIGED
- THE CONTRACTOR SHALL COORDINATE IN FURNISHING ALL MATERIAL AND WORK NOT PROVIDED BY THE UTILITY FOR COMPLETING ELECTRIC SERVICE INSTALLATION.
- 7, THE CONTRACTOR SHALL OBTAIN INSPECTION AND APPROVAL BY THE ENGINEER AND UTILITY COMPANY BEFORE BACKFILL AND/OR ENCLOSING ELECTRIC SERVICE INSTALLATION.