| ROUTE NO. | SECTION | | | COUNTY | SHEETS | SHEET NO. | |
|-----------------------|----------------------------|--------|---|-------------------|--------|--------------|--|
| የ.ኤ. ቴ 5154 | 유합. 5154 04-00343-00-BR | | W | INNEBAGO | 92 | 44 | |
| FED. RO | AD DIST. NO. 7 | ILLINO | s | FED. AID PROJECT- | BRM-50 | 99(75) | |

Structural Sheet 20A of 22A

NOTES

Bar splicer assemblies shall be of an approved type and shall develop in tension at least 125 percent of the yield strength of the lapped reinforcement bars. Splicer rods shall be of minimum 60 ksi yield strength, threaded or coiled full length.

All reinforcement bars shall be lapped and tied to the splicer rods or dowel bars. Bar splicer assemblies shall be epoxy coated according to the requirements for reinforcement bars.


Other systems of similar design may be submitted to the Engineer for approval. Approval shall be based on certified test results from an approved testing laboratory that the proposed bar splicer assembly satisfies the following requirements:

(Tension iii kips)
Minimum *Pull-out Strength = $0.66 \times fy \times A_t$ (Tension in kips)

Where fy = Yield strength of lapped reinforcement bars in ksi. A_t = Tensile stress area of lapped reinforcement bars.

* = 28 day concrete

| | BAR SPLIC | ER ASSEMBLI | ES |
|-----|------------------------------------|-------------|--|
| | 0 ! 0 / | Strengt | h Requirements |
| | Splicer Rod or Dowel Bar Length | | Min. Pull-Out Strength kips - tension |
| #4 | 1′-8′′ | 14.7 | 7.9 |
| #5 | 2'-0'' | 23.0 | 12.3 |
| #6 | 2'-7" | 33.1 | 17.4 |
| #7 | 3′-5′′ | 45.1 | 23.8 |
| #8 | 4'-6'' | 58.9 | 31.3 |
| #9 | 5′-9′′ | 75.0 | 39.6 |
| #10 | 7′-3′′ | 95.0 | 50.3 |
| #]] | 9'-0'' | 117.4 | 61.8 |





ROLLED THREAD DOWEL BAR

The diameter of this part

is the same as the diameter


of the bar spliced.



WELDED SECTIONS


BAR SPLICER ASSEMBLY ALTERNATIVES

**Heavy Hex Nuts conforming to ASTM A 563, Grade C, D or DH may be used.




INSTALLATION AND SETTING METHODS

"A": Set bar splicer assembly by means of a template bolt. "B" : Set bar splicer assembly by nailing to wood forms or cementing to steel forms. (E) : Indicates epoxy coating.



FOR INTEGRAL OR SEMI-INTEGRAL ABUTMENTS

| Min. | Capacity | = 23.0 | kips | - / | ensio | n | |
|------|----------|----------|------|-----|-------|---|---------|
| Min. | Pull-out | Strength | = 12 | 2.3 | kips | - | tension |



Required = 66

| | | Stage II Construction | Sta | Stage I Construction | |
|---|-------|---------------------------|-----|----------------------|--|
| Reinforcement Threaded or Coil Threaded or Coil Splicer Rods (E) Reinforce Bars Splicer Rods (E) Reinforce Bars | cemen | | - | | |

STANDARD

| | Bar Size | No. Assemblies Required | Location |
|--|-------------|----------------------------|----------|
| | | | |

BAR SPLICER ASSEMBLY DETAILS BELTLINE ROAD OVER ILLINOIS RAILNET FAU ROUTE 5154 SECTION 04-00343-00-BR WINNEBAGO COUNTY STA. 148+18.00 (S.N. 101-0172)