



\* Dimensions shall be determined by the Engineer in the field based on extent of deck deterioration at each drain.





## SECTION THRU EXISTING FLOOR DRAIN

Hatched area indicates concrete removal at floor drain replacement.

Cost included with Deck Slab Repair (Full Depth Type I)

## DRAIN REPLACEMENT DETAIL

Note: See "Bridge Deck Patching" plan sheets for Floor Drain replacement locations. See "Total Bill of Materials" for each structure for quantities.

Fiberglass pipe shall conform to ASTM D 2996, with short-time rupture strength hoop tensile stress of 30,000 p.s.i. minimum.

FILE NAME =	USER NAMÉ = swortzrw	DESIGNED -	REVISED -			
o:\pw_work\PWIDOT\SWARTZRW\dms36208\th	peledesign_94993.dgn	DRAWN -	REVISED ~			
	PLOT SCALE = 20.0000 '/ IN.	CHECKED -	REVISED -			
	PLOT DATE = 10/17/2008	DATE -	REVISED -			

STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION** 

	FLOO	R DRAI	N DETAIL	
N.	026-0003	(EB) &	SN. 026-0004	(WB)

SHEET NO. 8 8 SHEETS COUNTY TOTAL SHEET NO.

SECTION

| RIE. | SECTION | STEEL | SECTION | TO D-7 BRIDGE DECK REPAIRS | FAYETTE | 59 | 23 | CONTRACT NO. 94993 SCALE: N/A SHEET NO. 8 OF 8 SHEETS STA. ILLINOIS FED. AID PROJECT