FAI RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90	1314B	COOK	160	15
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CONTRACT 60293

TEMPORARY PAVEMENT MARKING - LINE 100MM

STATION		STATION		LENGTH	NET	COMMENT
STAGE I						
NAGLE AVENUE						
0+754.0	RT	0+837.7	RT	83.7	167.4	DOUBLE YEL
0+754.0	RT	0+837.7	RT	83.7	167.4	DOUBLE YEL
0+848.9	RT	0+944.3	RT	95.4	190.8	DOUBLE YEL
0+848.9	RT	0+874.6	RT	25.7	51.4	DOUBLE YEL
0+894.0	LT	0+950.0	RT	56.0	56.0	SOLID WHITE
0+955.0	LT	1+048.0	LT	93.0	93.0	SOLID WHITE
0+963.2	RT	1+034.4	RT	71.2	142.4	DOUBLE YEL
1+052.0	LT	1+229.0	LT	177.0	177.0	SOLID WHITE
1+056.3	RT	1+164.4	RT	108.1	216.2	DOUBLE YEL
GREGORY AVENUE						
4+474.0	RT	4+500.0	RT	26.0	26.0	SOLID WHITE
4+474.0	LT	4+502.0	LT	28.0	28.0	SOLID WHITE
4+415.0	LT	4+474.0	LT	59.0	59.0	SOLID WHITE
4+427.0	LT	4+452.0	LT	25.0	25.0	SOLID WHITE
4+350.0	LT	4+452.0	LT	102.0	102.0	SOLID WHITE
4+409.3	RT	4+474.0	RT	64.7	64.7	SOLID WHITE
4+516.1	RT	4+541.2	RT	25.1	50.2	DOUBLE YEL
BRYN MAWR AVENUE						
5+500.0	LT	5+525.0	LT	25.0	25.0	SOLID WHITE
5+500.0	RT	5+527.5	RT	27.5	27.5	SOLID WHITE
6+037.2		6+054.5		17.3	34.6	DOUBLE YEL
STAGE IB						
NAGLE AVENUE						
1+031.0	LT	1+040.0	RT	9.0	9.0	SOLID WHITE
1+048.0	LT	1+057.0	RT	9.0	9.0	SOLID WHITE
BRYN MAWR AVENUE						
5+500.0	LT	5+527.0	LT	27.0	27.0	SOLID WHITE
5+500.0	LT	5+525.0	LT	25.0	25.0	SOLID WHITE
STAGE II						
NAGLE AVENUE						
0+850.0	RT	0+950.0	RT	100.0	100.0	SOLID WHITE
1+052.0	RT	1+106.0	RT	54.0	54.0	SOLID WHITE
0+850.0	LT	0+940.3	LT	90.3	180.6	DOUBLE YEL
1+059.9	LT	1+242.8	LT	182.9	365.8	DOUBLE YEL
1+126.0	LT	1+242.8	LT	116.8	233.6	DOUBLE YEL
GREGORY AVENUE						
4+367.0	LT	4+462.5	LT	95.5	95.5	SOLID WHITE
4+425.0	LT	4+462.5	LT	37.5	37.5	SOLID WHITE
4+413.5	LT	4+486.0	LT	72.5	72.5	SOLID WHITE
4+500.0	LT	4+605.0	LT	105.0	105.0	SOLID WHITE
4+508.0	LT	4+570.0	LT	62.0	124.0	DOUBLE YEL
4+503.0	RT	4+530.0	RT	27.0	27.0	SOLID WHITE
BRYN MAWR AVENUE						
5+025.0	LT	5+153.0	LT	128.0	128.0	SOLID WHITE
5+032.9	LT	5+250.0	RT	217.1	434.2	DOUBLE YEL
5+054.0	LT	5+250.0	LT	196.0	392.0	DOUBLE YEL
5+025.0	RT	5+054.5	RT	29.5	29.5	SOLID WHITE
STAGE IIB						
NAGLE AVENUE						
1+047.0	RT	1+063.0	RT	16.0	16.0	SOLID WHITE
BRYN MAWR AVENUE						
5+025.0	LT	5+054.5	LT	29.5	29.5	SOLID WHITE
5+025.0	RT	5+037.0	RT	12.0	12.0	SOLID WHITE
5+032.0	LT	5+054.5	LT	22.5	45.0	DOUBLE YEL
			TOTAL =		4255	M

TEMPORARY PAVEMENT MARKING - LINE 600MM

STATION	LNGTH	COMMENT
STAGE I		
NAGLE AVENUE		
0+963.9	3.5	STOP BAR
0+944.3	3.5	STOP BAR
1+034.4	3.0	STOP BAR
1+056.5	4.5	STOP BAR
GREGORY AVENUE		
4+516.1	6.0	STOP BAR
4+487.4	3.6	STOP BAR
BRYN MAWR AVENUE		
6+037.2	6.2	STOP BAR
STAGE II		
NAGLE AVENUE		
0+940.3	3.1	STOP BAR
1+059.9	3.3	STOP BAR
GREGORY AVENUE		
4+485.0	7.0	STOP BAR
4+508.0	3.3	STOP BAR
BRYN MAWR AVENUE		
6+032.9	3.0	STOP BAR
STAGE IIB		
BRYN MAWR AVENUE		
6+032.0	3.5	STOP BAR
TOTAL =	54	M

TEMPORARY PAVEMENT MARKING - LINE 150MM

STATION		STATION		LENGTH	NET	COMMENT
STAGE I						
GREGORY AVENUE						
4+516.1	LT	4+541.2	LT	25.1	25.1	SOLID WHITE
BRYN MAWR AVENURE						
6+037.2	LT	6+054.5	LT	17.3	17.3	SOLID WHITE
STAGE II						
GREGORY AVENUE						
4+474.0	RT	4+484.0	RT	10.0	10.0	SOLID WHITE
				TOTAL =	52	M

PAVEMENT MARKING TAPE, TYPE III - LETTERS AND SYMBOLS

STATION	AREA	COMMENT
STAGE II		
NAGLE AVENUE		
0+980.0	2.13	ONLY
0+973.0	1.47	LEFT
1+017.0	2.13	ONLY
1+023.0	1.47	LEFT
TOTAL =	7	SQ M

PAVEMENT MARKING TAPE, TYPE III 100MM

STATION		STATION		LENGTH	NET	COMMENT
STAGE II						
NAGLE AVENUE						
0+959.1	LT	1+036.9	LT	77.8	155.6	DOUBLE YEL
0+957.0	LT	1+040.0	LT	83.0	83.0	SOLID WHITE
GREGORY AVENUE						
4+570.0	LT	4+605.0	LT	35.0	35.0	SOLID WHITE
				TOTAL =	274	M

PAVEMENT MARKING TAPE, TYPE III 150MM

STATION		STATION		LENGTH	NET	COMMENT
STAGE II						
NAGLE AVENUE						
0+959.1	LT	0+984.1	LT	25.0	25.0	SOLID WHITE
1+011.9	LT	1+036.9	LT	25.0	25.0	SOLID WHITE
				TOTAL =	50	M

PAVEMENT MARKING TAPE, TYPE III 600MM

STATION	LENGTH	COMMENT
STAGE II		
NAGLE AVENUE		
0+959.1	6.3	STOP BAR
1+036.9	6.1	STOP BAR
TOTAL =	12	METER

PAVEMENT MARKING TAPE, TYPE III 800MM

STATION	OFFSET		STATION	OFFSET		LENGTH	TOTAL	COMMENT
GREGORY AVENUE								
4+496.0	11	RT	4+501.0	11	RT	5.0	5.0	STOP BAR
4+489.0	8	LT	4+495.0	8	LT	6.0	6.0	STOP BAR
BRYN MAWR AVENUE								
5+517.0	9	RT	5+524.0	9	RT	7.0	7.0	STOP BAR
5+517.0	13	LT	5+521.0	13	LT	4.0	4.0	STOP BAR
						TOTAL =	22	METER

STORM SEWERS TO BE CLEANED

STRUCTURE	STATION	OFFSET(M)	STATION	OFFSET(M)	SIZE (MM)	LENGTH(M)
NAGLE AVENUE						
	0+845.5	0.0	0+951.8	0.3 RT	600	106.3
	0+875.0	6.0 LT	0+875.0	0.0	200	6.0
	0+875.0	6.0 RT	0+875.0	0.0	200	6.0
	0+961.0	8.6 RT	0+951.8	0.3 RT	250	12.4
	0+961.4	8.1 LT	0+951.8	0.3 RT	250	12.4
	1+035.0	8.2 LT	1+046.4	2.1 RT	250	14.6
	1+035.9	9.1 RT	1+046.4	2.1 RT	250	12.6
	1+049.0	0.0	1+142.0	0.0	525	93.0
	1+064.2	8.5 RT	1+064.2	0.0	200	8.5
	1+065.2	6.1 LT	1+065.2	0.0	200	6.1
	1+085.1	6.3 RT	1+064.2	8.5 RT	200	2.4
	1+148.5	7.5 RT	1+148.5	0.0	200	7.5
	1+149.0	6.4 LT	1+149.0	0.0	200	6.4
GREGORY AVENUE						
	4+400.0	0.5 RT	4+600.0	0.5 RT	1950	200.0
	4+440.0	4.5 RT	4+440.0	0.5 RT	300	4.0
	4+440.0	11.0 LT	4+440.0	0.5 RT	300	11.5
	4+545.6	4.5 RT	4+545.6	0.5 RT	250	4.0
	4+588.0	4.5 RT	4+588.0	0.5 RT	250	4.0
	4+560.7	4.1 LT	4+560.7	0.5 RT	250	4.6
BRYNMAWR AVENUE						
	5+425.0	0.5 RT	6+127.0	1.5 LT	2100	202.7
	5+472.0	6.5 RT	5+472.0	0.5 RT	200	6.0
	5+474.5	1.0 LT	5+525.3	2.5 LT	375	50.8
	5+505.0	4.6 LT	5+503.5	0.5 RT	250	5.3
	6+046.8	6.4 LT	6+046.8	1.5 LT	250	4.9
	6+104.0	6.5 RT	6+104.0	1.5 LT	200	8.0
	6+105.0	5.5 LT	6+105.0	1.5 LT	300	4.0
				TOTAL =		804.0

WORK ZONE PAVEMENT MARKING REMOVAL

STATION	OFFSET		STATION	OFFSET		LENGTH	WIDTH	AREA	COMMENT
STAGE I									
NAGLE AVENUE									
0+754.0		LT	0+894.0	LT		140.0	0.1	28.0	DOUBLE YEL
0+754.0		LT	0+874.6	LT		120.6	0.1	24.1	DOUBLE YEL
1+106.0		LT	1+151.4	LT		45.4	0.1	9.1	DOUBLE YEL
1+106.0		LT	1+229.0	LT		123.0	0.1	12.3	SOLID WHITE
GREGORY AVENUE									
4+415.0		LT	4+473.64	LT		58.6	0.1	5.9	SOLID WHITE
4+427.0		LT	4+454.0	LT		27.0	0.1	2.7	SOLID WHITE
4+389.0		LT	4+454.0	LT		65.0	0.1	6.5	SOLID WHITE
4+410.0		RT	4+473.64	RT		63.6	0.1	6.4	SOLID WHITE
STAGE II									
NAGLE AVENUE									
0+850.0		RT	0+894.0	RT		44.0	0.1	4.4	SOLID WHITE
0+850.0		LT	0+894.0	LT		44.0	0.1	8.8	DOUBLE YEL
0+959.8		LT	1+037.2	LT		77.4	0.1	15.5	DOUBLE YEL
0+957.0		LT	1+040.0	LT		83.0	0.1	8.3	SOLID WHITE
1+106.0		LT	1+244.2	LT		138.2	0.1	27.6	DOUBLE YEL
1+126.0		LT	1+244.2	LT		118.2	0.1	23.6	DOUBLE YEL
GREGORY AVENUE									
4+413.0		LT	4+473.64	LT		60.6	0.1	6.1	SOLID WHITE
4+570.0		LT	4+605.0	LT		35.0	0.1	3.5	SOLID WHITE
BRYN MAWR AVENUE									
6+054.5		RT	6+150.0	RT		95.5	0.1	9.6	SOLID WHITE
6+054.0		LT	6+250.0	LT		196.0	0.1	39.2	DOUBLE YEL
6+054.0		LT	6+250.0	LT		196.0	0.1	39.2	DOUBLE YEL
STAGE IIB									
BRYN MAWR AVENUE									
6+054.5		LT	6+145.0	LT		90.5	0.1	9.1	SOLID WHITE
SHOULDER CLOSURE									
4+350.0		LT	4+440.0	LT		90.0	0.1	9.0	SOLID WHITE
6+080.0		RT	6+180.0	RT		100.0	0.1	10.0	SOLID WHITE
STAGE II									
NAGLE AVENUE									
0+959.8		LT	0+981.5	LT		21.7	0.15	3.3	SOLID WHITE
1+011.5		LT	1+037.2	LT		25.7	0.15	3.9	SOLID WHITE
NAGLE AVENUE									
0+970.0								2.13	ONLY
0+962.0								1.47	LEFT
1+027.0								2.13	ONLY
1+035.0								1.47	LEFT
GREGORY AVENUE									
4+496.0		RT	4+501.0	RT		5.0	0.6	3.0	STOP BAR
4+486.0		LT	4+495.0	LT		9.0	0.6	5.4	STOP BAR
BRYN MAWR AVENUE									
5+517.0		RT	5+524.0	RT		7.0	0.6	4.2	STOP BAR
5+517.0		LT	5+521.0	LT		4.0	0.6	2.4	STOP BAR
							TOTAL =	338	SQ M

COLLINS ENGINEERS INC
123 N. WACKER DR., SUITE 300
CHICAGO, IL 60606
(312) 704-9300
ILLINOIS PROFESSIONAL DESIGN FIRM
LICENSE NO. 184-000993

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

F.A.I. 90 (I-90) AT NAGLE AVENUE

DRAWN BY: ML, DR, FD

DATE: DECEMBER 2004

CHECKED BY: JMH, MDK

FILE: G:\2724\CIVIL\EXHIBIT\NAGLE\2724014.dgn