

F. A. U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1621	06-00162-04-TL	COOK	012	002
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT CMM-9003(078)	

CONTRACT #63118

INDEX OF SHEETS

1.
- COVER SHEET
2.
- INDEX OF SHEETS, GENERAL NOTES & STATE STANDARDS
3.
- SUMMARY OF QUANTITIES
- 4.-7.
- STANDARD DISTRICT 1 TRAFFIC SIGNAL DESIGN DETAILS
8.
- PAVEMENT MARKING AND SIDEWALK PLAN
9.
- TRAFFIC SIGNAL INSTALLATION PLAN
10.
- CABLE PLAN & SCHEDULE OF QUANTITIES
11.
- MAST ARM MOUNTED STREET NAME SIGNS
12.
- DISTRICT 1 TYPICAL PAVEMENT MARKINGS

STATE STANDARDS

- 001001-02
- AREAS OF REINFORCEMENT BARS
- 424001-05
- CURB RAMPS FOR SIDEWALKS
- 701501-05
- URBAN LANE CLOSURE, 2L, 2W, UNDIVIDED
- 701502-03
- URBAN LANE CLOSURE, 2L, 2W, WITH BIDIRECTIONAL LEFT TURN LANE
- 701701-06
- URBAN LANE CLOSURE, MULTILANE INTERSECTION
- 701901-01
- TRAFFIC CONTROL DEVICES
- 720016-02
- MAST ARM MOUNTED STREET NAME SIGNS
- 780001-02
- TYPICAL PAVEMENT MARKINGS
- 805001-01
- ELECTRIC SERVICE INSTALLATION DETAIL
- 814001-02
- HANDHOLES
- 814006-02
- DOUBLE HANDHOLES
- 857001-01
- STANDARD PHASE DESIGNATION DIAGRAMS AND PHASE SEQUENCES
- 862001-01
- UNINTERRUPTIBLE POWER SUPPLY (UPS)
- 873001-02
- TRAFFIC SIGNAL GROUNDING & BONDING
- 876001-01
- PEDESTRIAN PUSH BUTTON POST
- 877011-04
- STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 16' THRU 55'
- 878001-07
- CONCRETE FOUNDATION DETAILS
- 880006-01
- TRAFFIC SIGNAL MOUNTING DETAILS

GENERAL NOTES:

EXISTING VILLAGE OWNED AND MAINTAINED UTILITY LINES ARE SHOWN ON THE PLANS TO INDICATE THEIR PRESENCE AND APPROXIMATE LOCATION. THE CONTRACTOR SHALL NOTIFY THE VILLAGE OF LANSING PUBLIC WORKS DEPARTMENT (708) 895-7190 TWO WEEKS PRIOR TO COMMENCING ANY EXCAVATION IN THE VICINITY OF THIS LINES. THE VILLAGE WILL THEN LOCATE AND MARK THE HORIZONTAL LOCATIONS OF THE LINES AND PROVIDE ANY AVAILABLE INFORMATION AS TO THEIR DEPTH. SHOULD ANY OF THE LINES BE DAMAGED BY THE CONTRACTOR'S OPERATION, THE CONTRACTOR SHALL REPAIR THEM TO THE SATISFACTION OF THE ENGINEER AND AT NO COST TO THE VILLAGE/STATE.

UTILITY LINES WERE PLOTTED FROM INFORMATION FURNISHED BY THE VARIOUS UTILITY COMPANIES INVOLVED AND THE ACCURACY SHOULD BE CONSIDERED APPROXIMATE ONLY.

UTILITY COMPANIES MAY BE ADJUSTING THEIR FACILITIES DURING CONSTRUCTION. THE CONTRACTOR SHALL COOPERATE WITH THESE ORGANIZATIONS WHILE THESE ADJUSTMENTS ARE BEING PREFORMED. J.U.L.I.E.-JOINT UTILITY LOCATION INFORMATION FOR EXCAVATORS SYSTEM (800) 892-0123 OR 811.

ALL EXISTING PAVEMENT MARKINGS THAT CONFLICT WITH THE PROPOSED PAVEMENT MARKINGS SHALL BE REMOVED BY THE CONTRACTOR. ALL COSTS ASSOCIATED WITH THIS WORK SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.

FILE NAME = 05012_04-INDX-01	USER NAME =	DESIGNED -- JMN	REVISED --	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	RIDGE ROAD & SCHOOL STREET INTERSECTION IMPROVEMENT INDEX OF SHEETS, GENERAL NOTES, & STATE STANDARDS		F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		CHECKED -- JMN	REVISED --				1621	06-00162-04-TL	COOK	012	002
	PLOT SCALE =	DRAWN -- PS	REVISED --				CONTRACT NO. 63118				
	PLOT DATE = 12-19-08	CHECKED -- AG	REVISED --				SCALE:	SHEET NO. 002 OF 012 SHEETS	STA.	TO STA.	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT CMM-9003(078)