2006

ENGINEER OF PROGRAM DEVELOPMENT

## INDEX OF SHEETS

1	COVER SHEET	STANDARDS		
2	INDEX, GENERAL NOTES, SIGNATURES, & SUMMARY OF QUANTITIES	701101-01 701106-01 701400-02		
3–9	EXISTING STRUCTURE PLANS	701402 <i>-05</i> 701406 <i>-0</i> 4 701411- <i>03</i> 701421- <i>01</i>		
GEN	ERAL NOTES	702001- <i>06</i>		

CLEANING AND PAINTING OF THE EXISTING STRUCTURAL STEEL SHALL BE AS SPECIFIED IN THE SPECIAL PROVISIONS FOR "CLEANING AND PAINTING EXISTING STEEL STRUCTURES". ALL EXISTING STEEL SHALL BE CLEANED PER NEAR WHITE BLAST CLEANING — SSPC—SP10. ALL EXISTING STEEL SHALL BE PAINTED ACCORDING TO THE REQUIREMENTS OF PAINT SYSTEM 1 — 02/E/U. THE COLOR OF THE FINAL FINISH COAT FOR EXTERIOR AND BOTTOM FLANGE OF THE FASCIA BEAMS SHALL BE INTERSTATE GREEN, MUNSELL NO 7.5G 4/8. THE COLOR OF THE FINAL FINISH COAT FOR ALL INTERIOR STEEL SURFACES SHALL BE GRAY, MUNSELL NO 5B 7/1.

THE SSPC-QP-1 AND SSPC-QP2 PAINTING CONTRACTOR CERTIFICATIONS WILL BE REQUIRED FOR THIS BRIDGE. THE USE OF AIR MONITORS WILL BE REQUIRED.

SUMMARY OF QUANTITIES				
ITEM #	DESCRIPTION	UNIT	QUANTITY	SFTY-2A
X0324401	PORTABLE TEMPORARY BARRIER SYSTEM, TEST LEVEL 3	FOOT	410	410
X0324402	RELOCATE PORTABLE TEMPORARY BARRIER SYSTEM, TEST LEVEL 3	FOOT	1230	1230
X7011420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	L SUM	1	1
50600600	CLEANING AND PAINTING STEEL BRIDGE, NO. 1	L SUM	1	1
50606400	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES	L SUM	1	1
67100100	MOBILIZATION	L SUM	1	1
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1
70100805	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	L SUM	1	1

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
DISTRICT 6

EXAMINED JONE 25 20 06

ENGINEER OF OPERATIONS

ENGINEER OF PROGRAM LIMPLEMENTATION

EXAMINED FEBRUARY 6

C-96-012-06

INDEX, GENERAL NOTES, SIGNATURES, & SUMMARY OF QTYS.