
## STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION



Contract Number: 74119




NEW SLAB

EXISTING SLAB

with Temporary Concrete Barrier.

## SECTIONS THRU SLAB

placed.



bars are in place and the concrete is ready to be

Wood Blocks — № 1"x7"x10" (ASTM A 36) └─Top Layer Splicer 2-5<sub>8</sub>" \$ Bolts

## DETAIL I

The 1"x7"x10" Plate shall not be removed until Stage II Construction forms and reinforcement bars are in place.

March 6, 2006 DESIGNED A.T.H. EXAMINED John a. Morris CHECKED S.J.B. DRAWN Drew Christopher CHECKED A.T.H. S.J.B. R-27

10-22-04

Top bars spacing Detail I 3′′ Detail II −@ <sup>7</sup>8″ ¢ Holes \* @ 1"x12" Notch

**NOTES** 

each barrier panel.

Cost of anchorage is included with Temporary Concrete Barrier.

Connect one (1) 1"x7"x10" steel £ to the top layer of couplers with 2-58" \$\phi\$ bolts screwed to coupler at approximate & of

Connect one (1) 1''x7''x10'' steel P to the concrete slab with  $2^{-5}e'' \phi$  Expansion Anchors or cast in place inserts spaced between the

top layer of reinforcement at approximate € of

Detail I - With Bar Splicer or Couplers:

—Extended #5 bars

each barrier panel. Detail II - With Extended Reinforcement Bars:

P 1"x7"x10"

\* Required only with Detail II

TEMPORARY CONCRETE BARRIER F.A.I. RT. 57 SOUTH BOUND OVER GREEN CREEK EFFINGHAM COUNTY SN 025-0004