### **GENERAL NOTES**

- 1. THE CONTRACTOR SHALL PROTECT AND CAREFULLY PRESERVE ALL SECTION OR SUBSECTION MONUMENTS OR PROPERTY OR REFERENCE MARKERS UNTIL THE OWNER, HIS AGENT, OR AN AUTHORIZED SURVEYOR HAS WITNESSED OR OTHERWISE
- 2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR CONTACTING THE OWNERS OF ALL EXISTING UTILITIES SO THAT THE UTILITIES AND THEIR APPURTENANCES MAY BE LOCATED AND ADJUSTED OR MOVED, IF NECESSARY, PRIOR TO THE START OF CONSTRUCTION OPERATIONS. THE CONTRACTOR SHALL COOPERATE WITH ALL UTILITY OWNERS AS PROVIDED IN THE STANDARD SPECIFICATIONS AND/OR SPECIAL PROVISIONS. UTILITY LOCATIONS ARE APPROXIMATE ONLY. THE CONTRACTOR SHALL USE CAUTION WHERE THERE ARE POTENTIAL CONFLICTS.
- 3. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL UNDERGROUND OR SURFACE UTILITIES EVEN THOUGH THEY MAY NOT BE SHOWN ON THE PLANS. ANY UTILITY THAT IS DAMAGED DURING CONSTRUCTION SHALL BE REPAIRED TO THE SATISFACTION OF THE ENGINEER OR THE OWNER OR REPLACED. THIS WORK SHALL BE AT THE CONTRACTOR'S EXPENSE.
- 4. THE CONTRACTOR SHALL PROTECT AND REPLACE ALL SIGNS REMOVED DURING CONSTRUCTION AS NEAR AS POSSIBLE TO THEIR ORIGINAL LOCATION, OR AS DETERMINED BY THE ENGINEER. THIS WORK SHALL BE INCLUDED IN THE COST OF THE CLEANING AND PAINTING CHAIN LINK FENCE PAY ITEM.
- 5. ALL SAW CUTTING SHALL BE INCLUDED IN THE UNIT COST OF THE PAY ITEM INDICATED FOR REMOVAL.
- 6.ALL CONSTRUCTION PERSONNEL WILL BE REQUIRED TO WEAR A FLUORESCENT VEST PER ARTICLE 701.12 AND 701.13 OF THE STANDARD SPECIFICATIONS AT ALL TIMES WHILE ON THE CONSTRUCTION SITE. COMPLIANCE WITH THIS REQUIREMENT SHALL
- 7. BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT 800-892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS FACILITIES. (48 HOURS NOTIFICATION IS REQUIRED)
- 8. BARRICADE: THE CONTRACTOR SHALL PROVIDE AND INSTALL TWO (2) WEIGHTED SANDBAGS ON EACH TYPE 1 OR TYPE II BARRICADE USED ONE (1) WEIGHTED SANDBAG ACROSS EACH BOTTOM RAIL.
- 9. THE CONTRACTOR SHALL NOTIFY VILLAGE PUBLIC WORKS AT LEAST 48 HOURS IN ADVANCE OF BEGINNING WORK TO OBTAIN VILLAGE UTILITY LOCATIONS AND SHALL COORDINATE ALL CONSTRUCTION OPERATIONS WITH THE ENGINEER.
- 10. MATERIALS RESULTING FROM THE REMOVAL OF SIDEWALK SHALL BE REMOVED AT THE END OF EACH DAY TO AN APPROVED SITE. IN THE JUDGMENT OF THE VILLAGE, SHOULD IT BE NECESSARY TO REMOVE SUCH MATERIALS, THE VILLAGE WILL HAVE THE MATERIAL REMOVED AND THE CONTRACTOR WILL BE BILLED (CHARGED) ACCORDINGLY.
- 11. THE CONTRACTOR MAY OBTAIN MUNICIPAL WATER IN BULK, AT NO CHARGE, AS LONG AS THERE IS NOT A "WATERING" BAN IN EFFECT. THE INDISCRIMINATE USE OF FIRE HYDRANTS IS STRICTLY PROHIBITED. WATER FOR CONSTRUCTION SHALL BE METERED OR OTHERWISE ACCOUNTED FOR AND A DAILY LOG MAINTAINED. THE CONTRACTOR SHALL PROVIDE THE WATER TRUCK AND DRIVER REQUIRED TO OBTAIN AND TRANSPORT THIS WATER. THE VILLAGE RESERVES THE RIGHT TO RESTRICT OR REFUSE THE USE OF VILLAGE WATER IF DEEMED NECESSARY.
- 12. IN AREAS WHERE THE EXISTING SIDEWALK TO BE REMOVED AND REPLACED, THE REMOVAL AND DISPOSAL OF ANY ADDITIONAL MATERIAL REQUIRED TO ESTABLISH THE PROPOSED SIDEWALK SUBGRADE ELEVATION SHALL BE INCLUDED IN THE PAY ITEM FOR PORTLAND CEMENT CONCRETE SIDEWALK REMOVAL AND REPLACEMENT.
- 13. THE CONTRACTOR SHALL LIMIT THE WORK TO ONE SIDE OF THE STREET UNLESS AS DIRECTED OTHERWISE BY THE ENGINEER.
- 14. ALL CONSTRUCTION SHALL BE DONE IN ACCORDANCE WITH THE DETAILS IN THE PLANS, THE SPECIAL PROVISIONS INCLUDED IN THE CONTRACT DOCUMENTS, AND THE LATEST EDITION OF THE FOLLOWING STATE OF ILLIMOIS SPECIFICATIONS: "THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION" (REFERRED TO AS THE "STANDARD SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS", THE "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS", THE "MANUAL OF TEST PROCEDURES FOR MATERIALS" AND THE "STANDARD SPECIAL PROVISIONS". IN THE "MANUAL OF TEST PROCEDURES FOR MATERIALS" AND THE "STANDARD SPECIAL PROVISIONS". SPECIFICATIONS FOR WATER AND SEWER MAIN CONSTRUCTION IN ILLINOIS".

#### **HIGHWAY STANDARDS** STANDARD NO.

000001-05	STANDARD SYMBOLS AND ABBREVIATIONS
635006-03	REFLECTOR AND TERMINAL MARKER PLACEMENT
635011-02	REFLECTOR MARKER AND MOUNTING DETAILS
701601-06	URBAN LANE CLOSURE, MULTILANE, 1W OR 2W, WITH NONTRANSVERSABLE MEDIAN
701801-04	LANE CLOSURE MULTILANE 1W OR 2W CROSSWALK OR SIDEWALK CLOSURE
701901-01	TRAFFIC CONTROL DEVICES



DESIGNED	~	AS	REVISED	-		
DRAWN	~	KAR	REVISED	-		
CHECKED	~*	TMS	REVISED	-	 	
DATE	~-	12-08-08	REVISED			1

# **VILLAGE OF RICHTON PARK, ILLINOIS FAU ROUTE 1632 (SAUK TRAIL)** STREETSCAPE

## **SUMMARY OF QUANTITIES**

					TOTAL QUANTITY
		CODE NO.	PAŸ ITEM	UNIT	CONSTRUCTION CODE YOUS
	#	42400430	PORTLAND CEMENT CONCRETE SIDEWALK, 5-INCH, SPECIAL	SQ FT	200
		44000600	SIDEWALK REMOVAL	SQ FT	1800
	#	44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	30
X	#	50600200	PAINTING STEEL RAILING	FOOT	400
		67100100	MOBILIZATION	L SUM	1
		70102630	TRAFFIC CONTROL & PROTECTION - STANDARD 701601	L SUM	1
		70102640	TRAFFIC CONTROL & PROTECTION - STANDARD 701801	L SUM	1
	#	78200410	GUARDRAIL MARKERS, TYPE A	EACH	6
	#	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2
Χ	#	81100220	CONDUIT ATTACHED TO STRUCTURE, 3/4" DIA., PVC COATED GALVANIZED STEEL	FOOT	470
Χ	#	81300220	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 6" X 6" X 4"	EACH	12
Χ	#	81700325	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 3-1/C NO. 8	FOOT	570
Χ	#	82107300	UNDERPASS LUMINAIRE, 150 WATT, HIGH PRESSURE SODIUM VAPOR	EACH	12
Χ	#	82500505	LIGHTING CONTROLLER, SPECIAL	EACH	1
Χ	#	84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	1
	#	LR430040	PAVING BRICK SIDEWALK	SQ YD	1350
Χ	#	X0323157	REMOVE LUMINAIRE FROM UNDERPASS	EACH	12
Χ	#	X0639515	CHAIN LINK FENCE REPAIR	FOOT	780
Х	#	XX001249	ORNAMENTAL FENCE	FOOT	1500
	#	XX005096	TRENCH FRAMES AND GRATES	FOOT	64
Χ	#	XX006767	LIQUIDTIGHT FLEXIBLE METAL CONDUIT, 3/4"	FOOT	50
		XX006783	SIGN PANEL, FURNISHED AND INSTALLED	EACH	10
	#	XX006991	BRICK FACADE	SQ FT	15500
Χ	#	XX008162	MAINTAIN LIGHTING SYSTEM	L SUM	1
	#	XX007448	CONCRETE EDGING 6" WIDE	FOOT	840
	#	Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1

X - SPECIALITY ITEM

SCALE:

# - SPECIAL PROVISION

#### INDEX OF SHEETS

1	COVER SHEET
2	GENERAL NOTES, SUMMARY OF QUANTITIES, INDEX OF SHEETS AND HIGHWAY STANDARDS
3	PLAN: SAUK TRAIL

- NORTH AND SOUTH ABUTMENT ELEVATIONS
- RETAINING WALL ELEVATIONS
- CENTER PIER ELEVATIONS

SHEET NO.

LIGHTING PLAN: SAUK TRAIL

TITLE

- STRUCTURAL DETAILS
- PIER, FENCE AND SIDEWALK DETAILS
- ELECTRICAL DETAILS
- DISTRICT ONE DETAIL TC-10: TRAFFIC CONTROL & PROTECTION FOR SIDE ROADS,

INTERSECTIONS AND DRIVEWAYS

GENERAL NOTES, SUMMARY OF QUANTITIES,				SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
INDEX OF SHEETS AND HIGHWAY STANDARDS			1632	06-00041-00-LS	соок	11	2
			CONTRACT NO. 63447				
	STA.	TO STA.	EED PO	DAD DIST NO THEINDIS SED A	ID DROJECT		