

STANDARD BAR SPLICER ASSEMBLY

Minimum Lap Lengths								
Bar size to be spliced	Table 1	Table 2	Table 3	Table 4				
3, 4	1'-5''	1'-11''	2'-1"	2'-4"				
5	1'-9''	2'-5"	2'-7"	2'-11"				
6	2'-1"	2'-11''	3'-1"	3'-6''				
7	2'-9"	3'-10''	4'-2"	4'-8''				
8	3′-8′′	5'-1''	5′-5″	6'-2''				
9	4'-7"	6'-5"	6'-10''	7'-9''				


Table I: Black bar, 0.8 Class C Table 2: Black bar, Top bar lap, 0.8 Class C Table 3: Epoxy bar, 0.8 Class C

Table 4: Epoxy bar, Top bar lap, 0.8 Class C

Threaded splicer bar length = min. lap length + $1_2^{\prime\prime}$ + thread length


* Epoxy not required on Bar Splicer Assembly components used in conjunction with black bars.

	Location	Bar		Table for minimum				
1	Locarion	size	required	lap length				
	081-0025	#5	14	Table 3				
	081-0025	#6	12	Table 3				



BAR SPLICER ASSEMBLY FOR #5 BAR ON INTEGRAL OR SEMI-INTEGRAL ABUTMENTS


No. required =




INSTALLATION AND SETTING METHODS

"A": Set bar splicer assembly by means of a template bolt.
"B": Set bar splicer assembly by nailing to wood forms or cementing to steel forms.

(E): Indicates epoxy coating.





STANDARD MECHANICAL SPLICER

Location	Bar size	No. assemblies required

NOTES
Splicer bars shall be deformed with threaded ends and have a minimum 60 ksi yield strength.

All reinforcement shall be lapped and tied to the splicer bars. Bar splicer assemblies shall be epoxy coated according to the requirements for reinforcement bars. See Section 508 of the Standard Specifications. See special provision for Mechanical Splicers.
See approved list of bar splicer assemblies and mechanical splicers for

BAR SPLICER ASSEMBLY AND MECHANICAL SPLICER DETAILS STRUCTURE NO. 018-0025

BSD-1

11-1-09

- 1													,	1
1	FILE NAME =	USER NAME = swartzrw	DESIGNED -	REVISED -	STATE OF ILLINOIS	BAR SPLICER ASSEMBLY DETAILS STRUCTURE NO. 018-0025			•	F.A.P RTF	SECTION	COUNTY	TOTAL SHEET	
	c:\pw_work\pwidot\swartzrw\dms53580\d77	346-sht-details.dgn	DRAWN -	REVISED -						116	(18-47HB-1)BR	CUMBERL AND	28 21	
		PLOT SCALE = 20.000000 '/ IN.	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION						CONTRACT	T NO. 74346	1	
		PLOT DATE = 3/19/2010	DATE -	REVISED -	SCAL		SHEET NO. 10 OF 12 SHEETS	STA.	TO STA.	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJE				1