INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	INDEX OF SHEETS, STANDARDS, AND GENERAL NOTES
3	SUMMARY OF QUANTITIES
4	CLASS D PATCH
5-9	BRIDGE REPAIR PLAN SHEETS
10	TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS

DISTRICT ONE TYPICAL PAVEMENT MARKINGS

LIST OF STATE STANDARDS

STANDARD NO. DE

DESCRIPTION

701301-02 LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS

701606*-05*

URBAN LANE CLOSURE, MULTILANE, 2W WITH MOUNTABLE MEDIAN

701901 TRAFFIC CONTROL DEVICES

GENERAL NOTES

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT 800-892-0123 OR 811 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS FACILITIES. (48 HOUR NOTIFICATION IS REQUIRED)

THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES AND THE VILLAGE OF ALSIP.

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.

THE RESIDENT ENGINEER SHALL CONTACT PATRICE HARRIS
AREA TRAFFIC FIELD ENGINEER AT (847) 715-8422 A MINIMUM OF 2
WEEKS PRIOR TO PLACEMENT OF PERMANENT PAVEMENT MARKING.

ALL DAMAGES TO EXISTING PAVEMENT MARKINGS OR RAISED REFLECTIVE PAVEMENT MARKERS OUTSIDE THE REMOVAL LINE SHOWN ON THE PLANS SHALL BE REPLACED AT NO ADDITIONAL COST TO THE DEPARTMENT

THE CONTRACTOR SHALL CONTACT THE DISTRICT ONE TRAFFIC CONTROL SUPERVISOR AT 847-705-4151 A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORK

THESE PLANS HAVE BEEN PREPARED FROM NOTES RECEIVED FROM BRIDGE INSPECTORS

DO NOT SCALE PLAN FOR CONSTRUCTION DIMENSIONS

IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.

WHEN ARTIFICIAL LIGHTING IS UTILIZED IN NIGHT OPERATIONS, THE CONTRACTOR SHALL EXERCISE THE UTMOST PRECAUTIONS IN PREVENTING ADVERSE VISIBILITY TO THE MOTORING PUBLIC AND ADJOINNG RESIDENTIAL AREAS

THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE ACCESS TO ABUTTING PROPERTY AT ALL TIMES DURING THE CONSTRUCTION OF THIS PROJECT.

THE CONTRACTOR SHALL ONLY SUPPORT THE TRANSVERE FLOOR BEAM ON ONE TEMPORARY SHORING TOWER AT A TIME. THE OTHER SUPPORT SHALL BE AN EXISTING OR PERMANENT BEARING. THE BEARINGS/ PEDESTALS ON THE EAST SIDE OF THE BRIDGE SHALL BE REPLACE FIRST.

THE CONTRACTOR IS, HEREBY, INFORMED THE THE BRIDGE HAS EXISTING ELECTRICAL CONDUITS FOR NAVIGATIONAL AND ROADWAY LIGHTS. CARE SHOULD BE TAKE NOT TO DAMAGE CONDUITS. ANY DAMAGE TO THESE CIRCUITS RESULTING FROM THE WORK RELATED TO THIS PROJECT SHALL BE REPAIRED AT NO ADDITIONAL COST TO IDOT

FILE	NAME	=			
c:\projects\d1319Ø6\d1319Ø6ea.dgn					

1	USER NAME = midyja	DESIGNED -	REVISED -
	*	DRAWN -	REVISED -
	PLOT SCALE = 50.00 '/ IN.	CHECKED -	REVISED -
	PLOT DATE = 4/4/2008	DATE -	REVISED -