TOTAL SHEETS SHEET NO. SHEET NO. 510 84 37 S13 sheets Permanent *** (1214 & 3127-1)RS-1 Contract 62343 Easement Existing R.O.W. Stone Riprap Class A4 (Typ.) —Top of Bank Existing R.O.W. Excavate and Backfill to Finished Grade El. 647.98 PLAN The alignment of the gabion wall may be adjusted in the field as directed by the Engineer. For Gabion Wall Details See Sht. Nos. S11 and S12 of S13. Legend: ILLINOIS DEPARTMENT OF TRANSPORTATION
HARLEM AVENUE (IL. 43) OVER BILL OF MATERIAL Exposed Gabion TINLEY CREEK
FAP ROUTE 348 SECTION (1214 & 3127-1)RS-1
COOK COUNTY STATION 20+29
STRUCTURE NO. 016-2400 Unit Total Cu. Yd. 3,691 Cu. Yd. 82.0 Structure Excavation

Gabions

Geotechnical Fabric for French Drains Sq. Yd. 66.0

DATE: JULY, 2003

CHANNEL MAINTENANCE PLAN

DRAWN BY: KAC CHECKED BY: PAS/DGS

COLLINS ENGINEERS, INC.

123 N. WACKER DR.
SUITE 300
CHICAGO, IL. 60606
(312)704-9300
ILLINOIS PROFESSIONAL DESIGN FIRM
LICENSE NO. 184-000993