| 17 | FAP<br>RTE |      | SE    | CTION |     |                | COUNTY | TO<br>SHE | SHEET |  |
|----|------------|------|-------|-------|-----|----------------|--------|-----------|-------|--|
|    | 338        | (113 | &     | 114)  | R-5 |                | WILL   | 5         | 16    |  |
|    | STA.       |      |       |       |     | T <sub>O</sub> | STA.   |           |       |  |
|    | FED. F     |      | BULDI | ors   | FAP | 338            | (IL    | RTE.      | 59)   |  |

|     | SUMMARY OF QUANTITIES |   |       |                   |                                      |   |  |   |   |  |  |  |                                      |
|-----|-----------------------|---|-------|-------------------|--------------------------------------|---|--|---|---|--|--|--|--------------------------------------|
|     |                       |   |       |                   | ROADWAY & DRAINAGE 80% FED 20% STATE | TRAFFIC<br>SIGNALS<br>IL 59 @<br>FEENEY/<br>FRASER<br>80% FED<br>10% STATE<br>10% VILLAGE | TRAFFIC<br>SIGNALS<br>IL 59 @<br>RENWICK<br>80% FED<br>10% STATE<br>10% COUNTY | TRAFFIC<br>SIGNALS<br>IL 59 @<br>FORT BEGGS<br>80% FED<br>13.3% STATE<br>6.7% VILLAGE | TRAFFIC SIGNALS<br>INTERCONNECT<br>80% FED<br>20% STATE | TRAFFIC SIGNALS<br>TEMPORARY<br>INTERCONNECT<br>80% FED<br>20% STATE | TRAFFIC<br>SIGNALS<br>EVP<br>EQUIPMENT<br>100% VILLAGE | WATER MAIN/<br>SANITARY<br>SEWER<br>100% VILLAGE | SIDEWALK<br>50% STATE<br>50% VILLAGE |
|     | CODE NO               | ITEM  | UNIT  | TOTAL<br>QUANTITY | J000-2A                              | Y031-1F   | Y031-1F  | Y031-1F   | Y031-1F   | Y031-1F  | Y031-3D  | Y060   | SFTY-IB                              |
| *   | XX006055              | MANHOLES, TYPE A, 7' DIAMETER, WITH 2 TYPE 1 FRAME, CLOSED<br>LID, RESTRICTOR PLATE | EACH  | 1                 | 1                                    |   |  |   |   |  |  |  |                                      |
| *   | XX006374              | DUCTILE IRON WATER MAIN 20" RESTRAINED JOINT TYPE                                   | FOOT  | 550               |                                      |   |  |   |   |  |  | 550  |                                      |
| *   | XX006642              | STORM SEWERS, (WATER MAIN REQUIREMENTS) TYPE 2, 15"                                 | FOOT  | 190               | 161                                  |   |  |   |   |  |  | 29   |                                      |
| *   | X0320815              | SLEEPER SLAB  | FOOT  | 1,383             | 1,383                                |   |  |   |   |  |  |  |                                      |
| *   | X0321193              | TEMPORARY CATCH BASINS  | EACH  | 12                | 12                                   |   |  |   |   |  |  |  |                                      |
| *   | X0321556              | SANITARY MANHOLES TO BE ADJUSTED  | EACH  | 21                |                                      |   |  |   |   |  |  | 21   |                                      |
| *   | X0321598              | MANHOLES, TYPE A, 6'-DIAMETER, WITH 2 TYPE 1 FRAME, CLOSED<br>LID. RESTRICTOR PLATE | EACH  | 4                 | 4                                    |   |  |   |   |  |  |  |                                      |
| *   | X0322256              | TEMPORARY INFORMATION SIGNING   | SQ FT | 538               | 538                                  |   |  |   |   |  |  |  |                                      |
| *   | X0322324              | WEED CONTROL, TEASEL  | POUND | 2                 | 2                                    |   |  |   |   |  |  |  |                                      |
| 0 * | X0322925              | ELECTRIC CABLE IN CONDUIT, TRACER NO. 14 1C   | FOOT  | 7,550             |                                      |   |  |   | 7,550   |  |  |  |                                      |
| *   | X0322938              | TEMPORARY END SECTION   | EACH  | 5                 | 5                                    |   |  |   |   |  |  |  |                                      |
| *   | X0323236              | TEMPORARY INLET   | EACH  | 2                 | 2                                    | -   |  |   |   |  |  |  |                                      |
| 0 * | X0323670              | PREFORMED DETECTOR LOOP   | FOOT  | 2,583             |                                      | 887   | 1,239  | 457   |   |  |  | -  |                                      |
| *   | X0323973              | SEDIMENT CONTROL, SILT FENCE  | FOOT  | 19,217            | 19,217                               |   |  |   |   |  |  |  |                                      |
| *   | X0323974              | SEDIMENT CONTROL, SILT FENCE MAINTENANCE  | FOOT  | 19,217            | 19,217                               |   |  |   |   |  |  |  |                                      |
| *   | X0323988              | TEMPORARY SOIL RETENTION SYSTEM   | SQ FT | 360               | 360                                  |   |  |   |   |  |  |  |                                      |
| *   | X0324439              | DUCTILE IRON WATER MAIN FITTINGS, 4" PLUG   | EACH  | 2                 |                                      |   |  |   |   |  |  | 2  |                                      |
| *   | X0324449              | DUCTILE IRON WATER MAIN FITTINGS, MECHANICAL JOINT 8" X 6" HYDRANT TEE              | EACH  | 1                 |                                      |   |  |   |   |  |  | 1  |                                      |
| *   | X0324688              | DUCTILE IRON WATER MAIN FITTINGS, 12', 11.25 DEGREE BEND                            | EACH  | 1                 |                                      |   |  |   |   |  |  | 1  |                                      |
| *   | X0324689              | DUCTILE IRON WATER MAIN FITTINGS, 12', 22.5 DEGREE BEND                             | EACH  | 3                 |                                      |   |  |   |   |  |  | 3  |                                      |
| o * | X0325705              | RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 2   | EACH  | 1                 |                                      |   |  |   | 1   |  |  |  |                                      |
| 0 * | X0325737              | TEMPORARY TRAFFIC SIGNAL TIMING   | EACH  | 2                 |                                      | .,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,   | 1  | 1   |   |  |  |  |                                      |
| *   | X0325846              | ABANDONMENT OF EXISTING WATER MAINS   | LSUM  | 1                 |                                      |   |  |   |   |  |  | 1  |                                      |

<sup>\*</sup> SPECIAL PROVISION

O SPECIALITY ITEM

○ CONSTRUCTION CODE Y080

VILLAGE = VILLAGE OF PLAINFILED COUNTY = WILL COUNTY ILLINOIS DEPARTMENT OF TRANSPORTATION DISTRICT NO. 1 SCHAUMBURG

SUMMARY OF QUANTITIES

Rev. 04-18-08 JCM SCALE NONE DATE MARCH 18, 2008

DRAWN BY JMH
CHECKED BY JCM