	CONTR	ACT NO.	6859
FAT SECTION	ON COUNTY	TOTAL	SHEE NO.
39.	WOODFORD	12	2
STA. VARIOUS	TO STA. VAR	RIOUS	
FEO. ROAD DIST. NO.	4 ILLINOIS FED. AL	PROJECT	r
- DA CONC MED	LAN DED 110 2006		

## COMMITMENTS

NO COMMITMENTS HAVE BEEN MADE FOR THIS PROJECT.

## GENERAL NOTES

MEDIAN REMOVAL SHALL BE DONE WITH JACKHAMMER METHOD FOR THE LENGTH OF THE DECK. REMOVAL SHALL NOT EXTEND BEYOND THE BRIDGE JOINTS. EXISTING REINFORCEMENT ANCHOR BARS JOINING THE MEDIAN TO THE DECK SHALL BE CLEANED, STRAIGHTENED AND REMAIN, TO BE TIED ONTO NEW EPOXY-COATED MEDIAN REINFORCEMENT. MEDIAN CONCRETE SHALL BE CONSTRUCTED ACCORDING TO SECTION 503.17 OF THE STANDARD SPECIFICATIONS AND REPLACED WITH SUPERSTRUCTURE, (BRIDGE MIX). USING DIRECTIVES IN SECTION 503.19, APPLY PROTECTIVE COAT TO DECKS, NEW MEDIANS, AND PARAPETS.

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION		
NAME	DATE	ILLINOIS OF WILMEIN	DE TRANSFORTATION	
		GENERAL	NOTES	
	sc.	LE: VERT.	DRAWN BY CE.	
	-OA		CHECKED BY	