FAI ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
255	(82-4I-5)-1R	ST. CLAIR	8	6
STA.		TO STA.		
CONTRACT NO.: 76571				

NOISEWALL SCHEDULE (RAMP E)

STATION	TO	STATION	BOTTOM OF PANEL ELEVATION	PANEL HEIGHT (FT)	TOP OF PANEL AND POST ELEVATION	TOTAL LENGTH OF POST (FT)
2+80	TO	2+82	448.38	4	452.38	8
2+82	TO	2+94	448.4	4	452.4	8
2+94	TO	3+06	448.47	6	454.47	11
3+06	TO	3+18	448.54	6	454.54	11
3+18	TO	3+30	448.61	6	454.61	11
3+30	TO	3+42	448.67	6	454.67	11
3+42	TO	3+54	448.73	6	454.73	11
3+54	TO	3+66	448.79	6	454.79	11
3+66	TO	3+78	448.85	6	454.85	11
3+78	TO	3+90	448.91	6	454.91	11
3+90	TO	4+02	448.96	6	454.96	11
4+02	TO	4+14	449.01	6	455.01	11
4+14	TO	4+26	449.06	6	455.06	11
4+26	TO	4+38	449.11	6	455.11	11
4+38	TO	4+50	449.16	6	455.16	11
4+50	TO	4+62	449.20	6	455.20	11
4+62	TO	4+74	449.24	6	455.24	11
4+74	TO	4+86	449.28	6	455.28	11
4+86	TO	4+98	449.32	6	455.32	11
4+98	TO	5+10	449.35	6	455.35	11
5+10	TO	5+22	449.40	6	455.40	11
5+22	TO	5+34	449.42	6	455.42	11
5+34	TO	5+46	449.45	6	455.45	11
5+46	TO	5+58	449.48	6	455.48	11
5+58	TO	5+70	449.51	6	455.51	11
5+70	TO	5+82	449.53	6	455.53	11
5+82	TO	5+94	449.55	6	455.55	11
5+94	TO	6+06	449.57	6	455.57	11
6+06	TO	6+18	449.59	6	455.59	11
6+18	TO	6+30	449.61	6	455.61	11
6+30	TO	6+42	449.62	6	455.62	11
6+42	TO	6+54	449.64	6	455.64	11
6+54	TO	6+66	449.65	6	455.65	11
6+66	TO	6+78	449.66	6	455.66	11
6+78	TO	6+90	449.69	6	455.69	11
6+90	TO	7+02	449.69	6	455.69	11
7+02	TO	7+14	449.70	6	455.70	11
7+14	TO	7+26	449.67	6	455.67	11
7+26	TO	7+38	449.67	6	455.67	11
7+38	TO	7+50	449.66	6	455.66	11
7+50	TO	7+62	449.65	6	455.65	11
7+62	TO	7+74	449.62	6	455.62	11
7+74	TO	7+86	449.59	6	455.59	11
7+86	TO	7+98	449.54	6	455.54	11
7+98	TO	8+10	449.49	6	455.49	11
8+10	TO	8+22	449.43	6	455.43	11
8+22	TO	8+34	449.24	6	455.24	11
8+34	TO	8+46	449.16	6	455.16	11
8+46	TO	8+58	449.08	6	455.08	11
8+58	TO	8+70	448.97	6	454.97	11
8+70	TO	8+82	448.86	6	454.86	11
8+82	TO	8+94	448.74	6	454.74	11
8+94	TO	9+06	448.63	6	454.63	11
9+06	TO	9+18	448.51	6	454.51	11
9+18	TO	9+30	448.39	6	454.39	11
9+30	TO	9+42	448.28	6	454.28	11
9+42	TO	9+54	448.16	6	454.16	11
9+54	TO	9+66	448.04	6	454.04	11
9+66	TO	9+78	447.92	6	453.92	11
9+78	TO	9+90	447.81	6	453.81	11
9+90	TO	10+02	447.69	6	453.69	11
10+02	TO	10+14	447.57	6	453.57	11
10+14	TO	10+26	447.45	6	453.45	11
10+26	TO	10+38	447.34	6	453.34	11
10+38	TO	10+50	447.20	6	453.20	11
10+50	TO	10+62	447.06	6	453.06	11
10+62	TO	10+74	446.90	6	452.90	11
10+74	TO	10+86	446.74	4	450.74	11
10+86	TO	10+88	446.56	4	450.56	8

NOISEWALL SCHEDULE (RIGHT SIDE)

STATION	TO	STATION	BOTTOM OF PANEL ELEVATION	PANEL HEIGHT (FT)	TOP OF PANEL AND POST ELEVATION	TOTAL LENGTH OF POST (FT)
777+86	TO	777+98	422.90	4	426.90	8
777+98	TO	778+10	422.87	6	428.87	11
778+10	TO	778+22	422.83	8	430.83	14
778+22	TO	778+34	422.79	10	432.79	16
778+34	TO	778+46	422.76	10	432.76	16
778+46	TO	778+58	422.72	10	432.72	16
778+58	TO	778+70	422.69	10	432.69	16
778+70	TO	778+82	422.65	10	432.65	16
778+82	TO	778+94	422.61	10	432.61	16
778+94	TO	779+06	422.58	10	432.58	16
779+06	TO	779+18	422.54	10	432.54	16
779+18	TO	779+30	422.51	10	432.51	16
779+30	TO	779+42	422.47	10	432.47	16
779+42	TO	779+54	422.43	10	432.43	16
779+54	TO	779+66	422.40	10	432.40	16
779+66	TO	779+78	422.36	10	432.36	16
779+78	TO	779+90	422.33	10	432.33	16
779+90	TO	780+02	422.30	10	432.30	16
780+02	TO	780+14	422.28	10	432.28	16
780+14	TO	780+26	422.27	10	432.27	16
780+26	TO	780+38	422.25	10	432.25	16
780+38	TO	780+50	422.23	10	432.23	16
780+50	TO	780+62	422.21	10	432.21	16
780+62	TO	780+74	422.19	10	432.19	16
780+74	TO	780+86	422.19	10	432.19	16
780+86	TO	780+93	422.16	10	432.16	16
780+93	TO	781+10	422.15	10	432.15	16
781+10	TO	781+22	422.12	10	432.12	16
781+22	TO	781+34	422.10	10	432.10	16
781+34	TO	781+46	422.09	10	432.09	16
781+46	TO	781+58	422.07	10	432.07	16
781+58	TO	781+70	422.06	10	432.06	16
781+70	TO	781+82	422.04	10	432.04	16
781+82	TO	781+94	422.02	10	432.02	16
781+94	TO	782+06	422.00	10	432.00	16
782+06	TO	782+18	421.98	10	431.98	16
782+18	TO	782+30	421.97	10	431.97	16
782+30	TO	782+42	421.94	10	431.94	16
782+42	TO	782+54	421.91	10	431.91	16
782+54	TO	782+66	421.90	10	431.90	16
782+66	TO	782+78	421.89	10	431.89	16
782+78	TO	782+90	421.90	10	431.90	16
782+90	TO	783+02	421.90	10	431.90	16
783+02	TO	783+14	421.92	10	431.92	16
783+14	TO	783+26	421.95	10	431.95	16
783+26	TO	783+38	421.98	10	431.98	16
783+38	TO	783+50	422.02	10	432.02	16
783+50	TO	783+62	422.07	10	432.07	16
783+62	TO	783+74	422.12	10	432.12	16
783+74	TO	783+86	422.20	10	432.20	16
783+86	TO	783+93	422.27	10	432.27	16
783+93	TO	784+10	422.36	10	432.36	16
784+10	TO	784+22	422.45	10	432.45	16
784+22	TO	784+34	422.54	10	432.54	16
784+34	TO	784+46	422.66	10	432.66	16
784+46	TO	784+58	422.77	10	432.77	16
784+58	TO	784+70	422.90	10	432.90	16
784+70	TO	784+82	423.03	10	433.03	16
784+82	TO	784+94	423.28	10	433.28	16
784+94	TO	785+06	423.33	10	433.33	16
785+06	TO	785+18	423.49	10	433.49	16
785+18	TO	785+30	423.66	10	433.66	16
785+30	TO	785+42	423.84	10	433.84	16
785+42	TO	785+54	424.02	10	434.02	16
785+54	TO	785+66	424.22	10	434.22	16
785+66	TO	785+78	424.41	10	434.41	16
785+78	TO	785+90	424.60	10	434.60	16
785+90	TO	786+02	424.80	10	434.80	16
786+02	TO	786+14	425.01	10	435.01	16
786+14	TO	786+26	425.23	8	433.23	14
786+26	TO	786+38	425.46	8	433.46	14
786+38	TO	786+50	425.69	8	433.69	14
786+50	TO	786+62	425.93	8	433.93	14
786+62	TO	786+74	426.18	8	434.18	14
786+74	TO	786+86	426.43	8	434.43	14
786+86	TO	786+98	426.71	8	434.71	14
786+98	TO	787+10	426.99	8	434.99	14
787+10	TO	787+22	427.27	8	435.27	14
787+22	TO	787+34	427.55	8	435.55	14
787+34	TO	787+46	427.83	8	435.83	14
787+46	TO	787+58	428.10	8	436.10	14
787+58	TO	787+70	428.38	8	436.38	14
787+70	TO	787+82	428.65	8	436.65	14
787+82	TO	787+94	428.92	8	436.92	14
787+94	TO	788+06	429.20	8	437.20	14
788+06	TO	788+18	429.44	8	437.44	14
788+18	TO	788+30	429.69	8	437.69	14
788+30	TO	788+42	429.93	8	437.93	14
788+42	TO	788+54	430.17	8	438.17	14
788+54	TO	788+66	430.40	8	438.40	14
788+66	TO	788+78	430.64	8	438.64	14
788+78	TO	788+90	430.88	8	438.88	14
788+90	TO	789+02	431.11	8	439.11	14
789+02	TO	789+14	431.34	8	439.34	14
789+14	TO	789+26	431.57	8	439.57	14
789+26	TO	789+38	431.78	8	439.78	14
789+38	TO	789+50	432.01	8	440.01	14
789+50	TO	789+62	432.23	8	440.23	14
789+62	TO	789+74	432.45	8	440.45	14
789+74	TO	789+86	432.67	8	440.67	14
789+86	TO	789+98	432.88	8	440.88	14
789+98	TO	790+10	433.10	8	441.10	14
790+10	TO	790+22	433.31	8	441.31	14
790+22	TO	790+34	433.52	8	441.52	14
790+34	TO	790+46	433.71	8	441.71	14
790+46	TO	790+58	433.96	8	441.96	14
790+58	TO	790+70	434.20	8	442.20	14
790+70	TO	790+82	434.45	8	442.45	14
790+82	TO	790+94	434.68	8	442.68	14
790+94	TO	791+06	434.92	8	442.92	14
791+06	TO	791+18	435.16	8	443.16	14
791+18	TO	791+30	435.39	8	443.39	14
791+30	TO	791+42	435.62	8	443.62	14
791+42	TO	791+54	436.97	6	442.97	11
791+54	TO	791+59	437.20	4	441.20	8

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

NOISEWALL SCHEDULE
RAMP E AND RIGHT SIDE

FAI ROUTE 255
SECTION (83-4I-5)1R
ST. CLAIR COUNTY

DRAWN BY:

PLOT DATE: *DATE-TIME*

PLAN		BY	DATE
NOTE BOOK NO.:	SURVEYED PLOTTED ALIGNMENT CHECKED RT. OF WAY CHECKED CADD FILE NAME		

$$DATE$$
DATE-TIME
DGN-SPEC
*REF-
*REF-
*REF-