



# **EXPANSION JOINT REHABILITATION DETAIL**

#### GENERAL NOTES:

- 1. THE NEW BITUMINOUS OVERLAY SHALL BE SAWED, REMOVED, AND THE JOINT AREA CLEANED. PRIOR TO PLACING THE HOT-POURED JOINT SEALER THE JOINT SHALL BE BLOWN OUT WITH COMPRESSED AIR.
- 2. THIS WORK SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE PER FOOT FOR EXPANSION JOINT REHABILITATION.




### BITUMINOUS SURF REM - BUTT JT



#### BITUMINOUS SURFACE REMOVAL TRANSITION

608+33 TO 608+63



NOTE: WHEN MILLING OPERATIONS PRODUCE A ROUNDED EDGE,
THEN A SAW CUT SHALL BE USED TO MANUFACTURE
A PERPENDICULAR EDGE AS SHOWN IN THE DETAIL,
THE ENGINEER SHALL BE THE SOLE JUDGE
CONCERNING THE USE OF THIS DETAIL

## **BITUMINOUS DETAIL AT BUTT JOINTS**

**DETAILS**