### **GENERAL NOTES**

- 1. ALL CONSTRUCTION SHALL BE DONE IN ACCORDANCE WITH THE DETAILS IN THE PLANS, THE SPECIAL PROVISIONS INCLUDED IN THE CONTRACT DOCUMENTS, AND THE LATEST EDITION OF THE FOLLOWING STATE OF ILLINOIS SPECIFICATIONS: "THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION" (REFERED TO AS THE "STANDARD SPECIFICATIONS"), THE "SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS", THE "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS" AND THE "MANUAL OF TEST PROCEDURES FOR MATERIALS".
- 2. THE CONTRACTOR SHALL HAVE THE RESPECTIVE UTILITY COMPANIES FIELD LOCATE ALL THEIR FACILITIES PRIOR TO BEGINNING CONSTRUCTION. THE CONTRACTOR SHALL ALSO VERIFY THE DEPTHS OF THE EXISTING UTILITIES IF NECESSARY, ALL RELOCATION OR LOWERING OF UTILITIES SHALL BE COORDINATED BY THE CONTRACTOR.
- 3. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL UNDERGROUND OR SURFACE UTILITIES EVEN THOUGH THEY MAY NOT BE SHOWN ON THE PLANS. ANY UTILITY THAT IS DAMAGED DURING CONSTRUCTION SHALL BE REPAIRED OR REPLACED AT THE CONTRACTOR'S EXPENSE TO THE SATISFACTION OF THE ENGINEER OR VILLAGE.
- 4. THE CONTRACTOR SHALL NOTIFY THE ENGINEER AT LEAST 48 HOURS IN ADVANCE OF BEGINNING WORK TO OBTAIN VILLAGE UTILITY LOCATIONS AND SHALL COORDINATE ALL CONSTRUCTION OPERATIONS WITH THE ENGINEER.
- 5. MATERIALS RESULTING FROM THE REMOVAL OF PAVEMENT, DRIVEWAYS, CURB AND GUTTER, HOT-MIX ASPHALT SURFACES, SIDEWALKS AND EXCAVATION FOR NEW SIDEWALKS ETC. SHALL BE REMOVED AT THE END OF EACH DAY TO AN APPROVED SITE. IN THE JUDGMENT OF THE VILLAGE, SHOULD IT BE NECESSARY TO REMOVE SUCH MATERIALS, THE VILLAGE WILL HAVE THE MATERIAL REMOVED AND THE CONTRACTOR WILL BE BILLED (CHARGED) ACCORDINGLY.
- 6. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL WATER REQUIRED FOR THIS PROJECT FROM AN
- 7. IT WILL BE THE CONTRACTOR'S RESPONSIBILITY TO NOTIFY RESIDENTS AND THE VILLAGE WHEN ACCESS TO THEIR DRIVEWAYS WILL BE TEMPORARILY CLOSED DUE TO DRIVEWAY REPLACEMENT. THE CONTRACTOR SHALL DISTRIBUTE NOTICES PROVIDED BY THE VILLAGE TO RESIDENTS, EVERY EFFORT SHALL BE MADE TO ACCOMMODATE ACCESS TO THESE PROPERTIES INCLUDING KNOCKING ON DOORS WHEN DRIVEWAYS ARE ABOUT TO BE CLOSED.
- 8. THE CONTRACTOR SHALL PROTECT AND CAREFULLY PRESERVE ALL SECTION OR SUBSECTION MONUMENTS OR PROPERTY OR REFERENCE MARKERS UNTIL THE OWNERS. HIS AGENT OR AN AUTHORIZED SURVEYOR HAS WITNESSED OR OTHERWISE REFERENCED THEIR LOCATIONS.
- 9. THE CONTRACTOR SHALL NOTIFY IDOT BUREAU OF MATERIALS (PHONE 847-705-4337) AT LEAST 24 HOURS PRIOR TO THE PLACEMENT OF HMA OR CONCRETE.
- 10. ANY SIGNS OR MAILBOXES THAT ARE IN CONFLICT WITH THE PROPOSED CONSTRUCTION SHALL BE REMOVED AND REPLACED IN ACCORDANCE WITH VILLAGE STANDARDS AND INCLUDED IN THE COST OF THE CONTRACT. MAIL SERVICE SHALL BE MAINTAINED AT ALL TIMES.
- 11. THE CONTRACTOR SHALL PROVIDE AND INSTALL TWO (2) WEIGHTED SANDBAGS ON EACH TYPE I OR TYPE II BARRICADE USED. ONE (1) WEIGHTED SANDBAG SHALL BE PLACED ACROSS EACH BOTTOM RAIL.
- 12. THE PRIME COAT APPLICATION RATE SHALL BE 0.1 GAL/SY.
- 13. ALL AGGREGATE USED ON THIS PROJECT SHALL BE CRUSHED MATERIAL.
- 14. THE DAYS PAVING OPERATION SHALL RESULT IN A SINGLE TRANSVERSE JOINT. ANY COLD LONGITUDINAL JOINTS WILL NOT BE ACCEPTED. PROVIDING A SINGLE TRANSVERSE JOINT SHALL BE ACCOMPLISHED BY PAVING ONE LANE OF SUFFICIENT LENGTH THAT WILL ALLOW FOR THE PAVING OF THE ADJACENT LANE IN THE SAME DAY.

- 15. THE CONTRACTOR SHALL UTILIZE A MECHANICAL SWEEPER TO CLEAN STREETS AFFECTED BY CONTRACTORS OPERATIONS, INCLUDING HAUL ROUTES, AT LEAST TWICE PER WEEK AND ADDITIONALLY AS DIRECTED BY THE ENGINEER. THIS WORK SHALL BE INCLUDED IN THE COST OF CONSTRUCTION.
- 16. NO DAMAGE TO PARKWAYS IS PLANNED AS PART OF THESE IMPROVEMENTS. ANY AND ALL RESTORATION OF DAMAGED PARKWAYS SHALL CONSIST OF NECESSARY SUB-GRADE MATERIAL AS APPROVED BY THE ENGINEER, TOPSOIL 4-INCH AND NATIVE SOD IN ACCORDANCE WITH SECTION 1081.03. RESTORATION SHALL BE INCLUDED IN THE PAY ITEM WHICH CAUSED THE DISTURBANCE.

<u> </u>					
EDGE OF HMA SHOULDER OR EDGE OF HMA PAVEMENT  PROPOSED AGGREGATE SHOULDERS, TYPE B  (TYP)	SEE NOTE 1. THIS DETAIL				
HMA SURFACE REMOVAL-BUTT JOINT HMA SURFACE COURSE, MIX "D", N70 - 1 1/2" LEVELING BINDER (MM), N70 3/4"	EXISTING HMA OR AGGREGATE DRIVEWAY  EXISTING ROW				

NOTES: 1. 5' MIN WHEN MATCHING EXISTING HMA DRIVEWAY 3' MIN. WHEN MATCHING EXISTING AGGREGATE DRIVEWAY

## HMA DRIVEWAY DETAIL

NO SCALE

SCALE: NONE

SECTION COUNTY 09-00046-00-RS STA. TO STA. FED. ROAD DIST. NO ILLINOIS C-91-725-09

\*FAU 0349 WALLIN DRIVE CONTRACT NO. 63226

# **INDEX OF SHEETS**

#### SHEET NO. TITLE

- COVER SHEET
- INDEX OF SHEETS, HIGHWAY STANDARDS, AND GENERAL NOTES 2
- SUMMARY OF QUANTITIES AND SCHEDULE OF QUANTITIES 3
- TYPICAL SECTIONS AND HMA MIXTURE REQUIREMENTS
- 5-7 RESURFACING AND PAVEMENT MARKING PLANS
- DISTRICT 1 DETAIL BD-32 BUTT JOINTS AND HMA TAPER DETAILS
- DISTRICT 1 DETAIL TC-10 TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS
- 10 DISTRICT 1 DETAIL - TC-13 DISTRICT ONE TYPICAL PAVEMENT MARKINGS
- 11 DISTRICT 1 DETAIL - TC-18 SIGNING FOR FLAGGING OPERATIONS AT WORK ZONE OPENINGS
- DISTRICT 1 DETAIL TC-22 ARTERIAL ROAD INFORMATION SIGN

## **HIGHWAY STANDARDS**

000001-05	STANDARD	SYMBOLS,	ABBREVIATIONS,	AND	PATTERNS

482011-03 HMA SHLD. STRIPS/SHLDS. WITH RESURFACING OR WIDENING AND RESURFACING PROJECTS

701011-02 OFF-RD MOVING OPERATIONS, 2L, 2W DAY ONLY

701301-03 LANE CLOSURE, 2L 2W, SHORT TIME OPERATIONS

701311-03 LANE CLOSURE, 2L 2W, MOVING OPERATIONS-DAY ONLY

701501-05 URBAN LANE CLOSURE, 2L,2W, UNDIVIDED

701801-04 LANE CLOSURE MULTILANE, 1W OR 2W CROSSWALK OR SIDEWALK CLOSURE

701901-01 TRAFFIC CONTROL DEVICES

780001-02 TYPICAL PAVEMENT MARKINGS

DESIGNED - JGH REVISED - IDOT REVIEW 6-29-09 DRAWN REVISED FILE NAME = Ø9Ø439-GenNotes.sht CHECKED - NJP REVISED PLOT DATE = 8/27/2009 DATE 05-22-09 REVISED

VILLAGE OF PLAINFIELD, ILLINOIS **FAU ROUTE 0349 WALLIN DRIVE** LAPP IMPROVEMENTS

INDEX OF SHEETS, HIGHWAY STANDARDS, **DETAILS AND GENERAL NOTES** 

STA.

SECTION COUNTY 09-00046-00-RS WILL 12 2 CONTRACT NO. 63226 FED. ROAD DIST. NO. FED. AID PROJECT