

## NOTES:

- 1. USE BLACK LETTERING ON ORANGE BACKGROUND.
- 2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
- 3. ERECT SIGN (1) WITH INSTALLED PANEL (2) ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
- 4. REMOVE PANEL 2 SOON AFTER THE START OF CONSTRUCTION.
- 5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
- 6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
- 7. SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

FILE NAME =	USER NAME = geglienobt	DESIGNED ~	REVISED - R. MIRS 09-15-97		ARTERIAL ROAD INFORMATION SIGN			F.A.U. RTF.	SECTION	COUNTY	TOTAL SHEET	
W:\d:ststd\22x34\tc22.dgn		DRAWN -	REVISED - R. MIRS 12-11-97	STATE OF ILLINOIS				1338 09	9-00034-00-RS	KANE	28 27	
	PLOT SCALE = 50.000 ' / IN.	CHECKED -	REVISED -T. RAMMACHER 02-02-99	DEPARTMENT OF TRANSPORTATION						TC-22	CONTRACT	T NO. 63292
	PLOT DATE = 1/4/2008	DATE -	REVISED - C. JUCIUS 01-31-07	O7 SCA	SCALE: NONE	SHEET NO. 1 OF 1 SHEETS	S STA.	TO STA.	FED. ROAD	DIST. NO. 1   ILLINOIS FED.	AID PROJECT AR	RA-9003 (306)

C-91-589-09