F.A.U. RTE.	SECTION		OUNTY	TOTAL	SHEET NO.	
1253	1253 Y-B-R-2		LAKE	17	2	
STA.		TO	STA.			
FED. ROAL	D DIST. NO.	ILLINOIS	FED. AID	PROJECT		

CONTRACT: 62768

INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	INDEX OF SHEETS, STATE STANDARDS, AND GENERAL NOTES
3	SUMMARY OF QUANTITIES
4~5	TRAFFIC CONTROL STAGING PLANS
6	DETOUR PLAN
7	GENERAL ROADWAY PLAN
8	ROADWAY AND PAVEMENT MARKING PLANS
9-15	BRIDGE PLANS (SN 049-0011)
16	TRAFFIC CONTROL AND PROTECTION FOR SIDEROADS, INTERSECTIONS, AND DRIVEWAYS

DISTRICT ONE TYPICAL PAVEMENT MARKINGS

STATE STANDARDS

000001-04 STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS

630001-06 STEEL PLATE BEAM GUARDRAIL

630201-03 PCC/BITUMINOUS STABILIZATION AT STEEL PLATE BEAM GUARDRAIL

631006-03 TRAFFIC BARRIER TERMINAL, TYPE 18

631031-05 TRAFFIC BARRIER TERMINAL, TYPE 6

701321-06 LANE CLOSURE, 2L, 2-W, BRIDGE REPAIR WITH BARRIER

702001-06 TRAFFIC CONTROL DEVICES

704001-02 TEMPORARY CONCRETE BARRIER

GENERAL NOTES

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT 800-892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS FACILITIES. (48 HOURS NOTIFICATION REQUIRED).

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.

THE RESIDENT ENGINEER SHALL CONTACT DEBBIE HANLON TRAFFIC FIELD ENGINEER, AT (847) 438-2300 A MINIMUM OF 2 WEEKS PRIOR TO PLACEMENT OF PERMANENT PAVEMENT MARKING.

IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSION & CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION & ORDERING OF MATERIALS.

ALL DAMAGE TO EXISTING PAVEMENT MARKINGS OR RAISED REFLECTIVE PAVEMENT MARKERS OUTSIDE THE REMOVAL LINE SHOWN ON THE PLANS SHALL BE REPLACED AT THE CONTRACTOR'S EXPENSE.

BEFORE BEGINNING ANY WORK, THE CONTRACTOR SHALL RETAIN AND RECORD (FOR FUTURE REFERENCES), ALL EXISTING PAVEMENT MARKING LINES (AND RAISED REFLECTIVE PAVEMENT MARKERS) IN ORDER THAT THESE LOCATIONS CAN BE RE-ESTABLISHED FOR STRIPING. EXACT LOCATIONS OF ALL STRIPING SHALL BE AS DIRECTED BY THE ENGINEER.

THE CONTRACTOR SHALL CONTACT THE DISTRICT ONE TRAFFIC CONTROL SURPERVISOR AT (847) 705-4470 FOR ARTERIAL A MINIMUN OF 72 HOURS IN ADVANCE OF BEGINNING WORK.

THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE ACCESS TO ABUTTING PROPERTY AT ALL TIMES DURING THE CONSTRUCTION OF THIS PROJECT.

THE CONTRACTOR SHALL ACCESS THE SITE FOR DEBRIS REMOVAL BY RAISING AND/OR LOWERING ALL EQUIPMENT AND MATERIAL OVER THE SIDE OF THE BRIDGE. THE CONTRACTOR WILL NOT BE ALLOWED OTHER ACCESS WITHOUT WRITTTEN PERMISSION FROM THE ENGINEER. THIS WORK WILL BE PAID FOR AT THE CONTRACTOR UNIT PRICE FOR DEBRIS REMOVAL.

THE CONTRACTOR MUST NOTIFY THE TRAFFIC SIGNAL ENGINEER (847-705-4424) AT LEAST ONE WEEK PRIOR TO IMPLEMENTING THE PROPOSED ONE-WAY DETOUR.

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATI						
NAME	DATE	ILLINOIS D		Of TRAISFORTALIZOR				
		HALF DAY RD	OVER E.	BRANCH	SKOKIE	DITCH		
		SN 049-0011						
			INDEX OF	CHEETS				
		LIST OF STATE STANDARDS						
		GENERAL NOTES						
		SCALE: VERT.		1	DRAWN BY			
		DATE		(CHECKED B	Y		

Lit UHIE = 6/38/2006 LE NAME = c:\projects\di23484\design_ee.dgn TS GOALE = 50.0000 / IN.