
STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION



Contract #64938

When cantilever forming brackets are used, the work shall be done according to Article 503.06, except as modified below and in the


details shown on this sheet.

The finishing machine rails shall be placed on the top flange of the exterior beams.


The beams or girders, supporting cantilever forming brackets, shall be tied together at 4 foot intervals.

For Standard construction, or Stage Construction the Hardwood bracing

materials shall be placed as shown between webs of beams in each bay.



FORM BRACES FOR STAGE CONSTRUCTION



FORM BRACES FOR STANDARD CONSTRUCTION

DESIGNED --CHECKED -DRAWN NO CHECKED JDA SB-1 10-22-04 CANTILEVER FORMING BRACKETS FAS ROUTE 2247 (U.S. 6) OVER BRUSH CREEK SECTION 13X-BR-1 BUREAU COUNTY STA. 1510+65.80 SN 006-0169