| F.A.U. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 7706 | (23-1)N,TS | LOGAN | 70 | 22 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT | | |

92611

| TEMPORARY PAVEMENT MARKING-LINE 5" | |
|---|---|
| (SKIP-DASH LINES, WHITE) | |
| LOCATION | QUANTITY (FOOT) |
| LINCOLN PARKWAY AT: | |
| RT STA 33+71.44 TO RT STA 45+14.49 | 286 |
| LT STA 33+71.44 TO LT STA 45+14.41 | 286 |
| TOTAL | 572 |

| THERMOPLASTIC PAVEMENT MARKING-LINE 8" | |
|---|---|
| LOCATION | QUANTITY (FOOT) |
| N.W. ISLAND OF INTERSECTION | 211 |
| S.W. ISLAND OF INTERSECTION | 179 |
| S.E. ISLAND OF INTERSECTION | 114 |
| TOTAL | 504.0 |

| THERMOPLASTIC PAVEMENT MARKING-LINE 5" | |
|---|---|
| (YELLOW LINE) | |
| LOCATION | QUANTITY (FOOT) |
| LINCOLN PARKWAY AT: | |
| LT STA 33+71.44 TO LT STA 39+00.00 | 528.6 |
| RT STA 33+71.44 TO RT STA 39+00.00 | 528.6 |
| AT MEDIAN NOSES | 60 |
| LT STA 40+26.56 TO LT STA 44+40.00 | 413.4 |
| RT STA 40+26.56 TO RT STA 44+40.00 | 413.4 |
| TOTAL | 1,944 |

| THERMOPLASTIC PAVEMENT MARKING-LINE 12" | |
|---|---|
| (YELLOW LINES @ 20' CTRS) | |
| LOCATION | QUANTITY (FOOT) |
| STA 8+00.67 TO STA 11+50.00 (5TH. STREET) | 89.1 |
| TOTAL | 89.1 |

| PREFORMED PLASTIC PAVT MARKING, TY B-LINE 24" | |
|---|---|
| (SOLID WHITE LINE) | |
| LOCATION | QUANTITY (FOOT) |
| RT STA 39+00.00 (LINCOLN PARKWAY) | 12.5 |
| RT STA 39+23.00 (LINCOLN PARKWAY) | 25 |
| LT STA 40+10.00 (LINCOLN PARKWAY) | 25 |
| LT STA 40+26.56 (LINCOLN PARKWAY) | 12.5 |
| RR CROSSING @ STA 44+50.00 | 56 |
| RT STA 18+60.00 (@ S. EVANS STREET) | 12 |
| STA 12+90.00 (5TH STREET) | 12 |
| STA 13+18.00 (5TH STREET) | 12 |
| STA 14+19.18 (5TH STREET) | 28 |
| STA 14+28.71 (5TH STREET) | 12 |
| AT POSTVILLE DRIVE | 12 |
| AT FRONTAGE ROAD | 20 |
| TOTAL | 239 |

| PREFORMED PLASTIC PAVT MARKING, TY B-LINE 5" | |
|---|---|
| (SKIP-DASH LINES, WHITE) | |
| LOCATION | QUANTITY (FOOT) |
| LINCOLN PARKWAY AT: | |
| RT STA 33+71.44 TO RT STA 45+14.49 | 286 |
| LT STA 33+71.44 TO LT STA 45+14.41 | 286 |
| TOTAL | 572 |

| RAISED REFLECTIVE PAVEMENT MARKER | |
|---|---|
| LOCATION | QUANTITY (EACH) |
| LINCOLN PARKWAY AT: | |
| STA 33+71.44 TO STA 45+14.44 (2 LINES) | 39 |
| TOTAL | 39 |

| REVISIONS | |
|---|---|
| NAME | DATE |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

c:\projects\d656402\drainagesheets.dgn
10/14/2003
*REF01

DG PROJECT: D656402 FILE: PLANSHEETS .DGN