SUMMARY OF QUANTITIES

ALL DIMENSIONS IN METERS EXCEPT PAY ITEMS AND UNLESS NOTED OTHERWISE

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80/94	2626.2-R-1	COOK	452	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CONTRACT NO. 62113 INDOT DES. NO. 0100987

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	ROADWAY • •	RETAINING WALLS • •	SURVEIL-LANCE • •	~~LIGHTING-ILLINOIS~~ Y030-1E •	INDIANA I000-2A • • •	BRIDGE OVER HOHMAN SFTY-2A • • •	BRIDGE OVER LITTLE CALUMET X071-2A • • •	BRIDGE OVER HARRISON SFTY-2A • • •	LIGHTING-INDIANA Y030-1E • • •			
				CONSTRUCTION TYPE CODE											
				I000-2A	Y007	Y032-1F	Y030-1E								
M2010210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	46	46	0	0	0	0	0	0	0	0			
M2010500	TREE REMOVAL, HECTARES	HA	.8	0	0	0	0	.8	0	0	0	0			
M2020010	EARTH EXCAVATION	CU M	2015.5	1135.4	0	0	0	880.1	0	0	0	0			
M2020045	EARTH EXCAVATION (SPECIAL)	CU M	1833.4	903.8	0	0	0	929.6	0	0	0	0			
M2021200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU M	3537.5	1699	0	0	0	1838.5	0	0	0	0			
M2040800	FURNISHED EXCAVATION	CU M	19400.3	17139.8	0	0	0	2260.5	0	0	0	0			
M2080150	TRENCH BACKFILL	CU M	1710.7	1384.8	0	0	0	325.9	0	0	0	0			
M2101000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ M	3890	3890	0	0	0	0	0	0	0	0			
M2113150	TOPSOIL FURNISH AND PLACE, 150MM	SQ M	3726	0	0	0	0	3726	0	0	0	0			
M2113300	TOPSOIL FURNISH AND PLACE, 300MM	SQ M	2412	2412	0	0	0	0	0	0	0	0			
M2114100	COMPOST FURNISH AND PLACE, 100MM	SQ M	2412	2412	0	0	0	0	0	0	0	0			
M2500210	SEEDING, CLASS 2A	HA	1	0	0	0	0	1	0	0	0	0			
M2500400	NITROGEN FERTILIZER NUTRIENT	KG	61.1	24.1	0	0	0	37	0	0	0	0			
M2500500	PHOSPHORUS FERTILIZER NUTRIENT	KG	61.1	24.1	0	0	0	37	0	0	0	0			
M2500600	POTASSIUM FERTILIZER NUTRIENT	KG	61.1	24.1	0	0	0	37	0	0	0	0			
M2500750	MOWING	HA	.7	.7	0	0	0	0	0	0	0	0			
M2510630	EROSION CONTROL BLANKET	SQ M	13977	1799	0	0	0	12178	0	0	0	0			
M2520110	SODDING, SALT TOLERANT	SQ M	2411.9	2411.9	0	0	0	0	0	0	0	0			
M2520200	SUPPLEMENTAL WATERING	UNIT	78	78	0	0	0	0	0	0	0	0			
M2800250	TEMPORARY EROSION CONTROL SEEDING	KG	137	48	0	0	0	89	0	0	0	0			
M3111300	SUB-BASE GRANULAR MATERIAL, TYPE B 300MM	SQ M	3890	3890	0	0	0	0	0	0	0	0			
M3120150	STABILIZED SUB-BASE 150MM	SQ M	3106	3106	0	0	0	0	0	0	0	0			
M4210360	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 360MM	SQ M	2156	2156	0	0	0	0	0	0	0	0			
M4214360	PAVEMENT REINFORCEMENT 360MM	SQ M	2156	2156	0	0	0	0	0	0	0	0			
M4400095	BITUMINOUS SURFACE REMOVAL 95MM	SQ M	3881	1438	0	0	0	2443	0	0	0	0			
M4401000	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ M	3031	875	0	0	0	2156	0	0	0	0			
M4402000	PAVEMENT REMOVAL	SQ M	93	0	0	0	0	93	0	0	0	0			
M4402010	DRIVEWAY PAVEMENT REMOVAL	SQ M	68.1	68.1	0	0	0	0	0	0	0	0			
M4402040	COMBINATION CURB AND GUTTER REMOVAL	METER	54	0	0	0	0	54	0	0	0	0			
M4402050	SIDEWALK REMOVAL	SQ M	40	0	0	0	0	40	0	0	0	0			
M4402060	APPROACH SLAB REMOVAL	SQ M	246	0	0	0	0	246	0	0	0	0			
M4402530	PAVED SHOULDER REMOVAL	SQ M	15017	6871	0	0	0	8146	0	0	0	0			

• SPECIALTY ITEMS

• • 100% STATE

• • • 100% INDIANA

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
I-80/94/US 6
KINGERY-BORMAN EXPRESSWAY
BURNHAM ROAD TO US 41
SUMMARY OF QUANTITIES

SCALE DRAWN BY ACE/CAD
DATE 07/04 CHECKED BY TAE

AMERICAN CONSULTING ENGINEERS

...\Sheets\ss1400218.dgn 08/18/2004 12:26:03 PM