ALL DIMENSIONS IN METERS EXCEPT PAY ITEMS AND UNLESS NOTED OTHERWISE

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80/94	2626.2-R-1	COOK	452	15
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CONTRACT NO. 62113 INDOT DES. NO. 0100987

SCHEDULE OF QUANTITIES

REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL

STATION	CUT/FILL(m°2	-	STATION	CUT/FILL(m°2	CU Meter
ILLINOIS					
THICKNESS	200.0 MM				
WESTBOUND - STAGE 1					
6+814.721	15.826	-	6+825.000	15.146	31.84
6+825.000	15.146	-	6+850.000	0.839	39.96
6+850.000	0.839	-	6+875.000	1.014	4.64
6+875.000	1.014	-	6+900.000	1.204	5.54
6+900.000	1.204	-	6+925.000	1.058	5.66
6+925.000	1.058	-	6+950.000	0.902	4.90
6+950.000	0.902	-	6+975.000	1.058	4.90
6+975.000	1.058	-	7+000.000	1.161	5.54
7+000.000	1.161	-	7+025.000	0.991	5.38
7+025.000	0.991	-	7+050.000	0.744	4.34
7+050.000	0.744	-	7+075.000	1.055	4.50
7+075.000	1.055	-	7+100.000	1.000	5.14
7+100.000	1.000	-	7+125.000	1.007	5.02
7+125.000	1.007	-	7+150.000	1.008	5.04
7+150.000	1.008	-	7+175.000	1.004	5.04
7+175.000	1.004	-	7+200.000	1.006	5.02
7+200.000	1.006	-	7+225.000	1.008	5.04
7+225.000	1.008	-	7+250.000	1.009	5.04
7+250.000	1.009	-	7+275.000	1.039	5.12
7+275.000	1.039	-	7+300.000	1.000	5.10
7+300.000	1.000	-	7+325.000	1.000	5.00
7+325.000	1.000	-	7+350.000	1.000	5.00
7+350.000	1.000	-	7+375.000	1.005	5.02
7+375.000	1.005	-	7+400.000	1.010	5.04
7+400.000	1.010	-	7+425.000	1.003	5.04
7+425.000	1.003	-	7+450.000	1.000	5.00
7+450.000	1.000	-	7+475.000	14.896	39.74
7+475.000	14.896	-	7+500.000	14.525	73.56
7+500.000	14.525	-	7+525.000	12.972	68.74
7+525.000	12.972	-	7+550.000	9.346	55.80
7+550.000	9.346	-	7+575.000	9.880	48.06
7+575.000	9.880	-	7+600.000	15.664	63.86
7+600.000	15.664	-	7+625.000	17.629	83.24
7+625.000	17.629	-	7+650.000	14.661	80.72
7+650.000	14.661	-	7+675.000	13.476	70.34
7+675.000	13.476	-	7+700.000	12.556	65.08
7+700.000	12.556	-	7+725.000	12.107	61.66
7+725.000	12.107	-	7+750.000	10.567	56.68
7+750.000	10.567	-	7+775.000	11.848	56.04
7+775.000	11.848	-	7+800.000	12.215	60.16
7+800.000	12.215	-	7+825.000	13.009	63.06
7+825.000	13.009	-	7+850.000	11.131	60.36
7+850.000	11.131	-	7+875.000	9.822	52.38
7+875.000	9.822	-	7+900.000	10.389	50.52
7+900.000	10.389	-	7+925.000	11.009	53.50
7+925.000	11.009	-	7+950.000	2.498	33.76
EASTBOUND - STAGE 1					
7+800.000	0.000	-	7+825.000	11.798	29.50
7+825.000	11.798	-	7+850.000	11.671	58.68
7+850.000	11.671	-	7+875.000	11.597	58.18
7+875.000	11.597	-	7+900.000	11.833	58.58
7+900.000	11.833	-	7+925.000	9.624	53.64
7+925.000	9.624	-	7+950.000	10.507	50.32
				SUBTOTAL =	1,699.0

REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL

STATION	CUT/FILL(m°2	-	STATION	CUT/FILL(m°2	CU Meter
INDIANA					
THICKNESS	200.0 MM				
WESTBOUND - STAGE 1					
7+950.000	2.498	-	7+975.000	2.641	12.84
7+975.000	2.641	-	8+000.000	3.271	14.78
8+000.000	3.271	-	8+025.000	2.877	15.38
8+025.000	2.877	-	8+050.000	0.000	7.20
EASTBOUND - STAGE 1					
7+950.000	10.507	-	7+975.000	13.189	59.24
7+975.000	13.189	-	8+000.000	12.979	65.42
8+000.000	12.979	-	8+025.000	14.025	67.50
8+025.000	14.025	-	8+050.000	16.250	75.68
8+050.000	16.250	-	8+075.000	17.619	84.68
8+075.000	17.619	-	8+100.000	16.304	84.80
8+100.000	16.304	-	8+125.000	18.664	87.42
8+125.000	18.664	-	8+150.000	17.387	90.12
8+150.000	17.387	-	8+175.000	21.751	97.84
8+175.000	21.751	-	8+200.000	15.968	94.30
8+200.000	15.968	-	8+225.000	0.000	39.92
EASTBOUND - STAGE 2					
8+250.000	0.000	-	8+275.000	20.801	52.00
8+275.000	20.801	-	8+300.000	17.607	96.02
8+300.000	17.607	-	8+325.000	16.677	85.72
8+325.000	16.677	-	8+350.000	14.640	78.30
8+350.000	14.640	-	8+375.000	14.118	71.90
8+375.000	14.118	-	8+400.000	13.981	70.24
8+400.000	13.981	-	8+425.000	14.654	71.58
8+425.000	14.654	-	8+450.000	0.000	36.64
8+575.000	0.000	-	8+600.000	14.175	35.44
8+600.000	14.175	-	8+625.000	13.006	67.96
8+625.000	13.006	-	8+650.000	12.335	63.36
8+650.000	12.335	-	8+675.000	11.493	59.58
8+675.000	11.493	-	8+700.000	12.158	59.12
8+700.000	12.158	-	8+725.000	12.623	61.96
8+725.000	12.623	-	8+750.000	0.000	31.56
				SUBTOTAL =	1,838.5

TOPSOIL FURNISH AND PLACE, 150MM

STATION	WIDTH(m)	-	STATION	WIDTH(m)	SQ METER
INDIANA					
7+960.549	3.400	-	7+978.397	3.100	58.0
7+991.232	3.850	-	8+074.943	7.820	488.5
8+074.943	7.820	-	8+100.000	7.820	195.9
8+100.000	7.820	-	8+150.000	7.820	391.0
8+150.000	7.820	-	8+175.000	9.820	220.5
8+175.000	9.820	-	8+196.500	9.820	211.1
8+196.500	16.120	-	8+206.358	16.120	158.9
8+206.358	9.820	-	8+218.600	9.820	120.2
8+218.600	9.820	-	8+223.664	0.000	67.8
8+246.867	0.000	-	8+259.040	13.100	126.0
8+259.040	7.820	-	8+275.000	7.820	124.8
8+275.000	7.820	-	8+330.000	5.950	378.7
8+330.000	5.950	-	8+419.700	5.950	533.7
8+419.700	17.500	-	8+443.287	17.500	412.8
8+443.287	17.500	-	8+470.500	0.000	238.1
8+614.836	5.850	-	8+745.985	5.850	767.2
				TOTAL =	3,726

TOPSOIL FURNISH AND PLACE, 300MM

STATION	WIDTH(m)	-	STATION	WIDTH(m)	SQ METER
ILLINOIS					
WESTBOUND					
7+609.543	9.000	-	7+619.436	4.500	66.8
7+619.436	4.500	-	7+700.000	5.300	394.8
7+700.000	5.300	-	7+800.000	5.900	560.0
7+800.000	5.900	-	7+870.150	8.000	487.5
7+870.150	8.000	-	7+895.539	8.000	203.1
EASTBOUND					
7+820.000	5.500	-	7+919.324	5.400	541.3
7+919.324	5.400	-	7+929.596	3.800	47.3
7+929.596	3.800	-	7+960.468	3.400	111.1
				TOTAL =	2,412

SEEDING, CLASS 2A

STATION	WIDTH(m)	-	STATION	WIDTH(m)	HECTARE
INDIANA					
SEE M2113150 TOPSOIL F&P 150					0.37
7+961.582	0.000	-	7+979.339	15.920	0.00
7+979.339	9.820	-	7+991.447	9.390	0.00
7+991.447	14.140	-	8+019.746	10.330	0.00
8+019.746	10.330	-	8+074.987	8.370	0.10
8+074.987	8.370	-	8+150.000	8.370	0.10
8+150.000	8.370	-	8+174.952	6.230	0.00
8+174.952	6.230	-	8+196.310	6.230	0.00
8+259.038	5.230	-	8+273.138	5.230	0.00
8+273.138	10.410	-	8+330.110	11.590	0.10
8+330.110	11.590	-	8+419.680	11.690	0.10
8+593.989	19.830	-	8+614.836	19.300	0.00
8+614.836	13.450	-	8+736.000	11.900	0.20
8+736.000	11.900	-	8+760.270	0.000	0.02
				TOTAL =	1.0

SODDING, SALT TOLERANT

STATION	WIDTH(m)	-	STATION	WIDTH(m)	SQ METER
ILLINOIS					
SEE M2113300 TOPSOIL F&P 300					2,411.9
				TOTAL =	2,411.9

SUB-BASE GRANULAR MATERIAL, TYPE B 300MM

STATION	WIDTH(m)	-	STATION	WIDTH(m)	SQ METER
ILLINOIS					
I-80/94/US 6 WB					
6+814.721	14.553	-	6+852.821	14.100	545.8
6+852.821	14.100	-	7+050.000	14.100	2,780.2
7+050.000	14.100	-	7+090.000	14.100	564.0
				TOTAL =	3,890

STABILIZED SUB-BASE 150MM

STATION	WIDTH(m)	-	STATION	WIDTH(m)	SQ METER
ILLINOIS					
I-80/94/US 6 WB					
6+814.721	11.704	-	6+852.821	11.250	437.3
6+852.821	11.250	-	7+050.000	11.250	2,218.3
7+050.000	11.250	-	7+090.000	11.250	450.0
				TOTAL =	3,106

CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 360MM

STATION	WIDTH(m)	-	STATION	WIDTH(m)	SQ METER
ILLINOIS					
I-80/94/US 6 WESTBOUND					
6+814.721	8.253	-	6+852.821	7.800	305.8
6+852.821	7.800	-	7+050.000	7.800	1,538.0
7+050.000	7.800	-	7+090.000	7.800	312.0
				TOTAL =	2,156

BITUMINOUS SURFACE REMOVAL 95MM

STATION	WIDTH(m)	-	STATION	WIDTH(m)	SQ METER
ILLINOIS					
EASTBOUND OUTSIDE SHOULDER					
7+550.000	3.300	-	7+750.000	3.600	690.0
7+750.000	3.600	-	7+957.691	3.600	747.7
				TOTAL =	1,438

BITUMINOUS SURFACE REMOVAL 95MM

STATION	WIDTH(m)	-	STATION	WIDTH(m)	SQ METER
INDIANA					
EASTBOUND OUTSIDE SHOULDER					
7+957.691	3.600	-	8+100.000	3.300	491.0
8+100.000	3.300	-	8+197.406	3.200	316.6
WESTBOUND OUTSIDE SHOULDER					
7+990.000	2.800	-	8+100.000	3.100	324.5
8+100.000	3.100	-	8+190.767	3.400	295.0
8+255.978	3.100	-	8+405.197	3.500	492.4
WESTBOUND INSIDE SHOULDER					
9+250.000	3.600	-	9+395.341	3.600	523.2
				TOTAL =	2,443

BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)

STATION	WIDTH(m)	-	STATION	WIDTH(m)	SQ METER
ILLINOIS					
I-80/94/US 6 WB INSIDE LANE					
7+600.000	2.500	-	7+750.000	2.500	375.0
7+750.000	2.500	-	7+950.000	2.500	500.0
				TOTAL =	875

BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)

STATION	WIDTH(m)	-	STATION	WIDTH(m)	SQ METER
INDIANA					
I-80/94/US 6 WB INSIDE LANE					
7+950.000	2.500	-	8+100.000	2.500	375.0
8+100.000	2.500	-	8+190.761	2.500	226.9
8+255.978	2.500	-	8+405.197	2.500	373.0
8+777.460	2.500	-	8+800.000	2.500	56.4
8+800.000	2.500	-	9+150.000	2.500	875.0
9+150.000	2.500	-	9+250.000	2.500	250.0
				TOTAL =	2,156

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
I-80/94/US 6
KINGERY-BORMAN EXPRESSWAY
BURNHAM ROAD TO US 41
SCHEDULE OF QUANTITIES

SCALE DRAWN BY ACE/CAD
DATE 07/04 CHECKED BY TAE

AMERICAN CONSULTING ENGINEERS

...\Sheets\sc14001a.rds 07/23/2004 07:42:10 AM