



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

October 26, 2004

SUBJECT: Various Routes
Section 2003-038 GRR
Various Counties
Item No. 29, November 5, 2004 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page 24 of the Special Provisions.
2. Revised the Cover Sheet of the Plans.
3. Added sheet 16A to the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Michael L. Hine
Engineer of Design
and Environment

A handwritten signature in cursive script, reading 'Ted B. Walschleger', followed by the letters 'P.E.' in a smaller font.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Diane O'Keefe; Roger Driskell; Jim White; Design & Environment File

TBW:MS:jc

This work will be paid for at the contract unit price each for "REPAIR TRAFFIC BARRIER TERMINAL TYPE 2".

When concrete is encountered poured around terminal posts, any additional work required in removing existing posts or installing new ones shall be paid for by using the item "Furnish and Set Steel Posts, Special" as described elsewhere in these special provisions and as specified by the Engineer.

REPAIR TRAFFIC BARRIER TERMINAL TYPE 3, SPECIAL

This work consists of removing damaged components of existing Traffic Barrier Type 3, Special in accord with the Standard Specifications and the locations as specified by the Engineer.

The Contractor shall adjust and realign rail element plates and posts adjacent to the traffic barrier terminal repaired, as directed by the Engineer. Unbolting, bolting, adjusting, realigning, excavating or any other work necessary to accomplish the desired realignment shall be included in the contract unit bid price for the pay items involved. This item shall also include the furnishing and installing of two (2) Direct Applied Reflectorized Terminal Markers which shall comply with the applicable portions of the contract special provisions for GUARDRAIL DELINEATION and the plans.

This work will be paid for at the contract unit price each for "REPAIR TRAFFIC BARRIER TERMINAL TYPE 3, SPECIAL".

When concrete is encountered poured around terminal posts, any additional work required in removing existing posts or installing new ones shall be paid for by using the item "Furnish and Set Steel Posts, Special" as described elsewhere in these special provisions and as specified by the Engineer.

REPAIR TRAFFIC BARRIER TERMINAL TYPE 4, 5, 5A, 6 AND 8

This work consists of removing and replacing damaged components of existing Traffic Barrier Terminals Type 4, 5, 6 and 8 in accord with the applicable portions of Section 630 of the Standard Specifications, Standards 631026, 631031, 631036 and the plans, at the locations as specified by the Engineer.

The Contractor shall adjust and realign existing rail element plates and posts adjacent to the traffic barrier terminal repaired, as directed by the Engineer. Unbolting, bolting, adjusting, realigning, excavating or any other work necessary to accomplish the desired realignment shall be included in the contract unit bid price for the pay items involved. This work shall also include any nonstandard sized or shaped blocks or hardware required to fit existing conditions.

This work will be paid for at the contract unit price each for "REPAIR TRAFFIC BARRIER TERMINAL", of the type specified.

Revised 10-26-2004