

GENERAL NOTES

1. SEE CROSS SECTIONS FOR SPECIAL SLOPES AND BACKSLOPES.
2. AT THE LOCATIONS WHERE EXCAVATION QUANTITIES ON THE PLANS ARE INDICATED AS HAVING BEEN ESTIMATED, THE ENGINEER WILL OBTAIN ORIGINAL AND FINAL CROSS SECTIONS TO DETERMINE PAY QUANTITIES.
3. THE REMOVAL OF BITUMINOUS SURFACING NOT ON A RIGID TYPE BASE REMOVED IN CONJUNCTION WITH THE BASE SHALL BE REMOVED AS EARTH EXCAVATION. THE REMOVAL OF BITUMINOUS SURFACING ON A RIGID TYPE BASE REMOVED IN CONJUNCTION WITH THE BASE SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR PAVEMENT REMOVAL.
4. IT IS ESTIMATED THAT 19,320 CUBIC YARDS OF EARTH WILL BE HAULED TO THE JOB FROM OUTSIDE THE PROJECT LIMITS. A SHRINKAGE FACTOR OF 15% HAS BEEN USED.
5. THE CONTRACTOR SHALL SEED ALL DISTURBED AREAS WITHIN THE PROJECT LIMITS. SEEDING CLASS 4 OR 6 (MODIFIED) SHALL BE USED, EXCEPT IN FRONT OF PROPERTIES WHERE THE GRASS WILL BE MOWED. THEN USE SEEDING, CLASS 1 (MODIFIED). CLASS 6 (MODIFIED) SHALL BE USED ON FRONT SLOPES AND DITCH BOTTOMS. CLASS 4 SHALL BE USED BEHIND TYPE A GUTTER, ON ALL BACKSLOPES AND AREAS BEHIND THE BACKSLOPE, AND BEYOND THE TOE OF FRONT SLOPE ON FILL SECTIONS WITHOUT DITCHES.
6. WHEN MULCH WITH EMULSIFIED ASPHALT IS APPLIED, IT WILL BE THE CONTRACTOR'S RESPONSIBILITY TO COVER OR PROTECT ALL TRAFFIC SIGNS, GUARDRAIL AND CURBS. ANY SIGNS, GUARDRAIL OR CURBS WHICH BECOME COVERED WITH ASPHALTIC MATERIAL SHALL BE CLEANED BY THE CONTRACTOR AT HIS OWN EXPENSE.
7. THE SUBGRADE ON THIS PROJECT, EXCLUSIVE OF ROCK CUT AREAS IS SCHEDULED TO BE IMPROVED TO A 12" DEPTH ACCORDING TO MECHANISTIC PAVEMENT DESIGN. THE AREAS SCHEDULED TO BE IMPROVED TO A DEPTH GREATER THAN 12" ARE ESTIMATED BASED ON THE ORIGINAL GEOTECHNICAL INVESTIGATION. THE SUBGRADE SHALL BE PROCESSED IN ACCORDANCE WITH ARTICLE 301 .03 OF THE STANDARD SPECIFICATIONS BEFORE THE ENGINEER SHALL DETERMINE THE LIMITS AND THE ADDITIONAL THICKNESS OF IMPROVEMENT REQUIRED, IF ANY.
8. EXCEPT FOR THE TOP 3", ALL AGGREGATE BASES AND SUBBASES 12" IN THICKNESS SHALL BE CONSTRUCTED OF AGGREGATE GRADATION CA-2. IF THE SPECIFIED THICKNESS EXCEEDS 12", THE BASES OR SUBBASES SHALL BE CONSTRUCTED OF TOPSIZE 6" BREAKER-RUN CRUSHED STONE WITH 15% TO 40% BY WEIGHT PASSING THE 2" SIZE SIEVE, EXCEPT FOR THE TOP 3". THE BREAKER-RUN CRUSHED STONE SHALL BE REASONABLY UNIFORMLY GRADED FROM COARSE TO FINE AND BE TAKEN FROM A QUARRY LEDGE CAPABLE OF PRODUCING CLASS "D" QUALITY AGGREGATE. THE TOP 3" SHALL BE GRADATION CA-6 OR CA-10 REGARDLESS OF THICKNESS. THE WATER NECESSARY TO ACHIEVE COMPACTION IN ALL BUT THE TOP 3" LAYER MAY BE ADDED AFTER THE SUBBASE OR BASE COURSE IS PLACED ON THE GRADE.
9. ALL EMBANKMENT CONSTRUCTED OF COHESIVE SOIL SHALL BE CONSTRUCTED WITH NOT MORE THAN 110% OF OPTIMUM MOISTURE CONTENT, DETERMINED BY THE STANDARD PROCTOR TEST. COHESIVE SOIL SHALL BE DEFINED AS ANY SOIL WHICH CONTAINS GREATER THAN 10% PARTICLES BY WEIGHT PASSING THE #200 SIEVE. THE 110% OF OPTIMUM MOISTURE LIMIT MAY BE WAIVED IN FREE-DRAINING GRANULAR MATERIAL WHEN APPROVED BY THE ENGINEER.
10. A NATIONWIDE 404 PERMIT HAS BEEN ISSUED FOR THIS PROJECT AND THE CONDITIONS OF THAT PERMIT MUST BE ADHERED TO.
11. THE NEW NUMBER FOR THIS STRUCTURE WILL BE 006-0163
12. THE CONTRACTOR SHALL SUBMIT FOUR COPIES OF THE REQUIRED SHOP DRAWINGS FOR REVIEW AND APPROVAL TO THE BUREAU OF BRIDGES AND STRUCTURES, 2300 SOUTH DIRKSEN PARKWAY, SPRINGFIELD, IL 62764. AFTER APPROVAL OF INITIAL SUBMITTAL, THE CONTRACTOR SHALL SUBMIT ONE SET OF SHOP DRAWINGS TO ERIC HARM, ENGINEER OF MATERIALS, 126 EAST ASH STREET, SPRINGFIELD, IL 62706, AND EIGHT (8) SETS OF SHOP DRAWINGS TO BE DISTRIBUTED TO:
- DISTRICT 2 DISTRICT ENGINEER (1)
FABRICATOR (1)
CONTRACTOR (2)
RESIDENT ENGINEER (2)
DISTRICT 2 BUREAU OF MATERIALS (2)
13. THE ADDITIONAL THICKNESS OF PROPOSED PAVEMENT REQUIRED TO MATCH THE BRIDGE APPROACH PAVEMENT, SHOWN IN STANDARD 420401, SHALL BE INCLUDED IN THE COST OF THE PROPOSED PAVEMENT AND NOT PAID FOR SEPARATELY.
14. EMBANKMENT QUANTITIES FOR THE CONSTRUCTION OF THE TRAFFIC BARRIER TERMINALS AS SHOWN IN THE PLANS ARE INCLUDED IN THE QUANTITIES FOR FURNISHED EXCAVATION.
15. THE CONTRACTOR SHALL SUPPLY THE RESIDENT ENGINEER WITH THE MANUFACTURER'S INSTALLATION REQUIREMENTS FOR THE TYPE OF STEEL PLATE BEAM GUARDRAIL TERMINAL TYPE 1 SPECIAL (FLARED).
16. ONE 8d GALVANIZED NAIL SHALL BE USED TO TOE NAIL THE WOOD BLOCK OUT TO THE WOOD POST ON ALL TRAFFIC BARRIER TERMINAL TYPE 1 SPECIALS.
17. THE CURB IS REQUIRED ON THE BRIDGE APPROACH PAVEMENT AS SHOWN ON STANDARD 420401 FROM THE BACK OF ABUTMENT TO THE BRIDGE APPROACH PAVEMENT DRAIN.
18. THE FOLLOWING MIXTURE REQUIREMENTS ARE APPLICABLE FOR THIS PROJECT:

BITUMINOUS MIXTURE DESCRIPTION

MIX USES	SURFACE COURSE	BINDER COURSE
PG	PG 58-22	PG 58-22
RAP% (MAX)	30	30
DESIGN AIR VOIDS(%)	3 @ N50	3 @ N50
MIXTURE COMPOSITION	IL 9.5 OR IL12.5	IL 19
FRICTION AGGREGATE	C	N/A
20 YEAR ESAL	0.03	0.03

19. THE CONTRACTOR WILL BE REQUIRED TO FURNISH 140 mm (5-1/2") HIGH BRASS STENCILS AS APPROVED BY THE ENGINEER AND INSTALL STATIONING AT 250' INTERVALS. STATIONING SHALL BE PLACED ON BOTH LANES OF 2-LANE HIGHWAYS AND ON THE OUTSIDE LANES IN BOTH DIRECTIONS OF 4-LANE HIGHWAYS. THE STATIONS SHALL BE PLACED 150 mm (6") INSIDE THE PAVEMENT MAKING EDGE SO THEY CAN BE READ FROM THE SHOULDER. THIS WORK WILL BE INCLUDED IN THE COST OF THE FINAL PAVEMENT SURFACE.
20. WHERE FIELD TILE IS ENCOUNTERED, STORM SEWER OR PIPE DRAIN WILL BE USED IN ACCORDANCE WITH SECTION 611. THE MINIMUM SIZE FOR REPLACEMENT WILL BE 150 mm (6") FOR PIPE DRAINS AND 200 mm (8") FOR STORM SEWER, BUT THE SIZE MUST BE AT LEAST 50 mm (2") LARGER THAN THE ADJOINING TILE. A FIELD TILE JUNCTION VAULT WILL BE CONSTRUCTED AT THE RIGHT-OF-WAY TO CONNECT THE TILE TO THE STORM SEWER.
21. THE FINISHED SURFACE OF THE PAVEMENT SHALL BE TESTED IN ACCORDANCE WITH ARTICLE 407.09(a).
22. PAVEMENT MARKING SHALL BE DONE ACCORDING TO STANDARD 780001, EXCEPT AS FOLLOWS:
1. ALL WORDS, SUCH AS ONLY, SHALL BE 8 FEET HIGH.
 2. ALL NON-FREEWAY ARROWS SHALL BE THE LARGE SIZE.
 3. THE DISTANCE BETWEEN YELLOW NO-PASSING LINES SHALL BE 8", NOT 7" AS SHOWN IN THE DETAIL OF TYPICAL LANE AND EDGE LINES.
23. PERMANENT SURVEY MARKERS, TYPE II SHALL BE SET AT INTERVALS OF 2,000 FEET OR AS DIRECTED BY THE ENGINEER. THE PERMANENT SURVEY MARKERS, TYPE II SHALL BE CAST-IN-PLACE AS SHOWN ON HIGHWAY STANDARD 667101.
24. RIGHT-OF-WAY MARKERS WILL BE ERECTED WITH THE BACK FACE OF THE MARKER ON THE RIGHT-OF-WAY LINE UNLESS THE NEW RIGHT-OF-WAY LINE HAS BEEN SURVEYED AND PINNED. IN WHICH INSTANCE THE RIGHT-OF-WAY MARKERS WILL BE ERECTED 12 INCHES INSIDE THE NEW RIGHT-OF-WAY LINE.
25. THE ENGINEER SHALL SUBMIT TO THE SURVEY CREW A DESCRIPTION OF LOCATION, ELEVATION, AND COORDINATES FOR EACH PERMANENT SURVEY MARKER.
26. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING UTILITY PROPERTY DURING CONSTRUCTION OPERATIONS AS OUTLINED IN ARTICLE 107.31 OF THE STANDARD SPECIFICATIONS. A MINIMUM OF 48 HOURS ADVANCE NOTICE IS REQUIRED FOR NON-EMERGENCY WORK. THE JULIE NUMBER IS 800-892-0123. THE FOLLOWING LISTED UTILITIES LOCATED WITHIN THE PROJECT LIMITS OR IMMEDIATELY ADJACENT TO THE PROJECT CONSTRUCTION LIMITS ARE MEMBERS OF JULIE:
- ILLINOIS POWER COMPANY MR. TIMOTHY MCTAGGART (815)-224-6270
MEDIACOM MR. BOB LARKIE (309)-944-5621
SBC/AMERITECH TELEPHONE COMPANY MR. JEREMY SCHNACK (309)-793-4456
VERIZON MR. KALIN HINSHAW (815)-895-1515
27. CADD DATA WILL BE AVAILABLE TO CONTRACTORS AND CONSULTANTS WORKING ON THIS PROJECT. THIS INFORMATION WILL BE PROVIDED UPON REQUEST AS MICROSTATION CADD FILES AND GEOPAK COORDINATE GEOMETRY FILES ONLY. IF DATA IS REQUIRED IN OTHER FORMATS IT WILL BE YOUR RESPONSIBILITY TO MAKE THESE CONVERSIONS. IF ANY DISCREPANCY OR INCONSISTENCY ARISES BETWEEN THE ELECTRONIC DATA AND THE INFORMATION ON THE HARD COPY, THE INFORMATION ON THE HARD COPY SHOULD BE USED. CONTACT THE DISTRICT'S PROJECT ENGINEER TO REQUEST THESE FILES.
28. THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES.
29. THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.
30. ALL DIMENSIONS SHOWN ARE IN FEET UNLESS OTHERWISE NOTED. PAVEMENT THICKNESS, CULVERT SIZE, CONDUIT SIZE AND MARKING WIDTHS ARE SHOWN IN INCHES UNLESS NOTED.
31. WHERE SECTION OR SUB-SECTION MONUMENTS ARE ENCOUNTERED, THE ENGINEER SHALL BE NOTIFIED BEFORE SUCH MONUMENTS ARE REMOVED. THE CONTRACTOR SHALL PROTECT AND CAREFULLY PRESERVE ALL MONUMENTS OR OTHERWISE REFERENCE THEIR LOCATION. THE CONTRACTOR WILL BE RESPONSIBLE FOR HAVING AN AUTHORIZED SURVEYOR RE-ESTABLISH ANY SECTION OR SUB-SECTION MONUMENTS DESTROYED BY HIS OPERATIONS.
32. ONLY THOSE TREES DESIGNATED BY THE ENGINEER SHALL BE REMOVED. THE CONTRACTOR SHALL PROTECT ALL REMAINING TREES FROM DAMAGE DUE TO HIS OPERATIONS.
33. TREE PLACEMENT LAYOUT SHALL BE PERFORMED BY THE DISTRICT LANDSCAPE ARCHITECT. MULCH SHALL BE HARDWOOD WOOD CHIP, 5 FOOT WIDTH, 4 INCHES THICK WITH WEED BARRIER FABRIC. ALTERNATE SITE: TBD BY DISTRICT 2.
34. ALL SAW CUTTING OF EXISTING PAVEMENT SHALL BE CONSIDERED INCLUDED IN PAVEMENT REMOVAL. THE MINIMUM SAW CUT DEPTH IN THE PAVEMENT SHALL BE FULL DEPTH OF THE EXISTING PAVEMENT UNLESS OTHERWISE SPECIFIED IN A DETAIL IN THE PLANS OR THE ENGINEER.
35. THE CONTRACTOR SHALL REMOVE AND DISPOSE OF ALL CORRUGATED METAL PIPE CULVERTS AS SHOWN IN THE PLANS. COST OF THE WORK TO BE INCLUDED IN THE CONTRACT UNIT PRICE FOR EARTH EXCAVATION.
36. REMOVAL OF EXISTING BITUMINOUS SURFACE (OIL AND CHIP), AGGREGATE BASE COURSE AND AGGREGATE SHOULDERS SHALL BE CONSIDERED INCLUDED IN THE COST OF EARTH EXCAVATION.
37. ACCORDING TO IDOT BDE PROCEDURE MEMORANDUM 99-34 AND OPERATIONS POLICY 5-1800, ALL UNMOWED AREAS SHOULD BE DESIGNATED IN THE PLANS AND SEEDED WITH THE APPROPRIATE NATIVE SEEDING SELECTIONS FROM CLASS 4, PER DIRECTIVE OF THE DECEMBER 8, 1999 STUDIES AND PLANS ENGINEER'S MEMORANDUM.
38. THRUST BLOCKS SHALL BE MADE OF CLASS SI CONCRETE AND SHALL BEAR AGAINST UNDISTURBED EARTH.
39. AN ESTIMATED QUANTITY FOR CLASS 4 SEEDING, FERTILIZER, MULCH METHOD 2 AND PERIMETER EROSION BARRIER IS INCLUDED IN THE CONTRACT FOR USE AT THE CONTRACTOR'S BORROW SITE AS NEEDED.

POLICY GUIDELINES:

ALL TREES REMOVED FROM THE PROJECT AREA (6 TREES, MAX.) FOR CONSTRUCTION OR MAINTENANCE PURPOSES WILL BE REPLACED WITH DECIDUOUS TREE SPECIES WHICH ARE NATIVE TO THE DISTRICT 2 AREA. TREES WILL BE REPLACED ACCORDING TO THE IDOT DEPARTMENTAL POLICY D & E - 18 (SEPTEMBER 18, 2002). THE LOCATION OF THE REPLACEMENT TREES SHALL BE DETERMINED BY THE DISTRICT 2 LANDSCAPE ARCHITECT.

ALL ENTRANCES SHALL HAVE NO LESS THAN 1:4 SIDE SLOPES PER DISTRICT STANDARD 20.1.

COMMITMENTS:

NONE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SBI 88 (NEW BEDFORD ROAD
OVER GREEN RIVER)
SECTION 103C-BR
BUREAU COUNTY
GENERAL NOTES

DRAWN BY: HLC

REVISIONS	
NAME	DATE

PLAN	DATE	BY
	REVISION	
	NO. OF WAY CHECKED	
	NO. OF FILE NAME	