TREE REPLACEMENT SCHEDULE

						0 1 10
F. A. RTE.	SECTION		COUNTY		TOTAL SHEETS	SHEET NO
88	103C-BR		BUREAU		51	40
STA. 19+00				TO STA. 39+00		
FED. ROAD DIST. NO.		ILLINOIS		FED. AID PROJECT		

GENERAL NOTES:

- 1. TREE LAYOUT SHALL BE PERFORMED BY THE DISTRICT LANDSCAPE ARCHITECT.
- 2. MULCH SHALL BE HARDWOOD WOOD CHIPS, 5 FOOT WIDTH, 4 INCHES THICK WITH WEED BARRIER FABRIC.
- 3. ALTERNATE SITE: TBD BY DISCTRICT 2.

SCIENTIFIC NAME	COMMON NAME	SIZE	UNIT	LOCATION	QUANTITY
TREE, QUERCUS BICOLOR	SWAMP WHITE OAK	1-3/4" CALIPER, BALLED & BURLAPPED	EACH	SEE ABOVE NOTE	6
			,		
				-	

ALL DIMENSIONS ARE IN MILLIMETERS (INCHES)
UNLESS OTHERWISE NOTED.