

GENERAL NOTES

| ROUTE NO. | SEC. | COUNTY | TOTAL SHEETS | SHEET NO. |
|---------------------|----------|---------|--------------|-----------|
| FAP 303 (IL 173) | 130-M | Boone | 114 | 9 |
| FED ROAD DIST. NO. | ILLINOIS | PROJECT | | |

CONTRACT NO. 64533

The application portions of Article 105.07 of the Standard Specification shall apply except for the following: The Contractor shall be responsible to locate the vertical depths of the underground utilities which may interfere with construction operations. This work will not be measured or paid for separately, but shall be considered as included in the unit bid price for the item of construction involved.

Per SB 699 (90 day utility relocation law) – Once right-of-way is clear to award the project, a notice will be sent to the utility companies instructing them to have their facilities relocated within 90 days. Estimated date relocation complete = Letting Date + 135 days.

Following are the known utilities located within the project limits or immediately adjacent to the project construction limits which are not members of JULIE and should be notified individually by the contractor:

CADD data will be available to Contractors and Consultants working on this project. This information will be provided upon request as MicroStation CADD files and Geopak coordinate geometry files ONLY. If data is required in other formats it will be your responsibility to make these conversions. If any discrepancy or inconsistency arises between the electronic data and the information on the hard copy, the information on the hard copy should be used. Contact the District's Project Engineer to request these files.

Lateral distances from the centerline on all inlets are to the face of the inlet.

All proposed manholes on this project shall be cast in place or precast. This work will be paid for at the contract unit price Each for MANHOLE of the type and size specified.

A quantity for Aggregate Surface Course Type B, has been added to the plans for temporary access while the existing entrances are under construction and shall be used as directed by Engineer.

The cost of removal and disposal of material from the Temporary Pavement Patch shall be included in Aggregate Base Course, Type B.

COMMITMENTS

1. The deciduous trees on Jerry L. and Mary Ann Peters' property will be saved and will be shown on the contract plans to be saved. This is a commitment made to the property owner by the Project Engineer.
2. The District shall contact the Village of Poplar Grove to ensure the coordination of the installation of a water main and sanitary sewer line prior to or concurrently with the project.
3. The Contractor shall allow the tenants of the Ronald Argyle and E.C. Stephens property access to off street parking during construction.

Program #5
(Arch. Size)
Enlarge
200%
Enlarge 107%