

SCHEDULE OF QUANTITIES

20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)		21400100	GRADING AND SHAPING DITCHES		25000600	POTASSIUM FERTILIZER NUTRIENT	
UNIT	LOCATION	REMARK'S	FOOT	LOCATION	REMARK'S	POUND	LOCATION	REMARK'S
10	STA. 1479+12 47' RT	E. MOLINE RD.	50	LT. STA. 510+40 TO 510+90	IL 78 / MOLINE RD.	3	LT. STA. 510+40 TO 510+90	IL 78 / MOLINE RD.
14	STA. 55+14 9' RT	3RD ST.	50	RT. STA. 510+40 TO 510+90	IL 78 / MOLINE RD.	2	RT. STA. 510+40 TO 510+90	IL 78 / MOLINE RD.
24	TOTAL		50	LT. STA. 522+25 TO 522+75	IL 78 / MOLINE RD.	2	LT. STA. 522+25 TO 522+75	IL 78 / MOLINE RD.
			50	RT. STA. 522+25 TO 522+75	IL 78 / MOLINE RD.	2	RT. STA. 522+25 TO 522+75	IL 78 / MOLINE RD.
			50	LT. STA. 555+25 TO 555+75	IL 78 / MOLINE RD.	2	LT. STA. 555+25 TO 555+75	IL 78 / MOLINE RD.
			50	RT. STA. 555+25 TO 555+75	IL 78 / MOLINE RD.	2	RT. STA. 555+25 TO 555+75	IL 78 / MOLINE RD.
			50	LT. STA. 569+75 TO 570+25	IL 78 / MOLINE RD.	2	LT. STA. 569+75 TO 570+25	IL 78 / MOLINE RD.
			50	RT. STA. 569+75 TO 570+25	IL 78 / MOLINE RD.	2	RT. STA. 569+75 TO 570+25	IL 78 / MOLINE RD.
			400	TOTAL		88	LT. STA. 417+00 TO 438+50	IL 78 (SOUTH)
						79	RT. STA. 417+00 TO 438+50	IL 78 (SOUTH)
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)		25000400	NITROGEN FERTILIZER NUTRIENT		1	LT. STA. 438+50 TO 439+50	IL 78 (SOUTH)
UNIT	LOCATION	REMARK'S	POUND	LOCATION	REMARK'S	1	RT. STA. 438+50 TO 439+50	IL 78 (SOUTH)
24	STA. 484+15 55' LT	IL 78 / MOLINE RD.	3	LT. STA. 510+40 TO 510+90	IL 78 / MOLINE RD.	6	LT. STA. 439+50 TO 445+50	IL 78 (SOUTH)
22	STA. 484+11 92' LT	IL 78 / MOLINE RD.	2	RT. STA. 510+40 TO 510+90	IL 78 / MOLINE RD.	5	RT. STA. 439+50 TO 445+50	IL 78 (SOUTH)
25	STA. 484+08 61' LT	IL 78 / MOLINE RD.	2	LT. STA. 522+25 TO 522+75	IL 78 / MOLINE RD.	5	RT. STA. 445+50 TO 460+00	IL 78 (SOUTH)
31	STA. 503+16 28' RT	IL 78 / MOLINE RD.	2	RT. STA. 522+25 TO 522+75	IL 78 / MOLINE RD.	8	RT. STA. 445+50 TO 460+00	IL 78 (SOUTH)
26	STA. 503+32 29' RT	IL 78 / MOLINE RD.	2	LT. STA. 555+25 TO 555+75	IL 78 / MOLINE RD.	18	LT. STA. 475+00 TO 479+50	IL 78 (SOUTH)
37	STA. 503+77 28' RT	IL 78 / MOLINE RD.	2	RT. STA. 555+25 TO 555+75	IL 78 / MOLINE RD.	11	RT. STA. 475+00 TO 479+50	IL 78 (SOUTH)
29	STA. 583+74 24' RT	IL 78 (NORTH)	2	LT. STA. 569+75 TO 570+25	IL 78 / MOLINE RD.	47	LT. STA. 479+50 TO 482+50	IL 78 (SOUTH)
22	STA. 1482+89 44' RT	E. MOLINE RD.	2	RT. STA. 569+75 TO 570+25	IL 78 / MOLINE RD.	35	RT. STA. 479+50 TO 482+50	IL 78 (SOUTH)
17	STA. 1481+67 38' RT	E. MOLINE RD.	2	LT. STA. 417+00 TO 438+50	IL 78 (SOUTH)	58	LT. STA. 484+00 TO 496+50	IL 78 / MOLINE RD.
21	STA. 1479+47 47' RT	E. MOLINE RD.	88	RT. STA. 417+00 TO 438+50	IL 78 (SOUTH)	56	RT. STA. 484+00 TO 496+50	IL 78 / MOLINE RD.
19	STA. 1478+75 47' RT	E. MOLINE RD.	79	LT. STA. 438+50 TO 439+50	IL 78 (SOUTH)	59	LT. STA. 1475+50 TO 1483+60	E. MOLINE RD.
19	STA. 1478+33 48' RT	E. MOLINE RD.	1	RT. STA. 438+50 TO 439+50	IL 78 (SOUTH)	44	RT. STA. 1475+50 TO 1483+60	E. MOLINE RD.
17	STA. 54+70 74' LT	3RD ST.	1	LT. STA. 439+50 TO 445+50	IL 78 (SOUTH)	52	LT. STA. 50+41 TO 56+50	3RD ST.
309	TOTAL		1	RT. STA. 439+50 TO 445+50	IL 78 (SOUTH)	24	RT. STA. 50+41 TO 56+50	3RD ST.
			6	LT. STA. 445+50 TO 460+00	IL 78 (SOUTH)	11	LT. STA. 0+50 TO 2+50	MOHAWK RD.
			5	RT. STA. 445+50 TO 460+00	IL 78 (SOUTH)	16	RT. STA. 0+50 TO 2+50	MOHAWK RD.
			8	LT. STA. 475+00 TO 479+50	IL 78 (SOUTH)	641	TOTAL	
			18	RT. STA. 475+00 TO 479+50	IL 78 (SOUTH)			
			11	LT. STA. 479+50 TO 482+50	IL 78 (SOUTH)	25000910	SEEDING, CLASS 1 (MODIFIED)	
			47	RT. STA. 479+50 TO 482+50	IL 78 (SOUTH)	ACRE	LOCATION	REMARK'S
			35	LT. STA. 484+00 TO 496+50	IL 78 / MOLINE RD.	0.01	LT. STA. 438+50 TO 439+50	IL 78 (SOUTH)
			56	RT. STA. 484+00 TO 496+50	IL 78 / MOLINE RD.	0.05	RT. STA. 439+50 TO 445+50	IL 78 (SOUTH)
			59	LT. STA. 1475+50 TO 1483+60	E. MOLINE RD.	0.52	LT. STA. 479+50 TO 482+50	IL 78 (SOUTH)
			44	RT. STA. 1475+50 TO 1483+60	E. MOLINE RD.	0.39	RT. STA. 479+50 TO 482+50	IL 78 (SOUTH)
			52	LT. STA. 50+41 TO 56+50	3RD ST.	0.64	LT. STA. 484+00 TO 496+50	IL 78 / MOLINE RD.
			24	RT. STA. 50+41 TO 56+50	3RD ST.	0.62	RT. STA. 484+00 TO 496+50	IL 78 / MOLINE RD.
			11	LT. STA. 0+50 TO 2+50	MOHAWK RD.	0.66	LT. STA. 1475+50 TO 1483+60	E. MOLINE RD.
			16	RT. STA. 0+50 TO 2+50	MOHAWK RD.	0.49	RT. STA. 1475+50 TO 1483+60	E. MOLINE RD.
			641	TOTAL		0.58	LT. STA. 50+41 TO 56+50	3RD ST.
						0.27	RT. STA. 50+41 TO 56+50	3RD ST.
						0.12	LT. STA. 0+50 TO 2+50	MOHAWK RD.
						0.17	RT. STA. 0+50 TO 2+50	MOHAWK RD.
						4.52	TOTAL	
20100500	TREE REMOVAL, ACRES		25000500	PHOSPHORUS FERTILIZER NUTRIENT		25001830	SEEDING, CLASS 6 (MODIFIED)	
ACRE	LOCATION	REMARK'S	POUND	LOCATION	REMARK'S	ACRE	LOCATION	REMARK'S
0.47	LT. STA. 485+65 TO 491+89	IL 78 / MOLINE RD.	3	LT. STA. 510+40 TO 510+90	IL 78 / MOLINE RD.	0.03	LT. STA. 510+40 TO 510+90	IL 78 / MOLINE RD.
0.11	RT. STA. 485+25 TO 487+97	IL 78 / MOLINE RD.	2	RT. STA. 510+40 TO 510+90	IL 78 / MOLINE RD.	0.02	RT. STA. 510+40 TO 510+90	IL 78 / MOLINE RD.
0.02	RT. STA. 1483+17 TO 1483+42	E. MOLINE RD.	2	LT. STA. 522+25 TO 522+75	IL 78 / MOLINE RD.	0.02	LT. STA. 522+25 TO 522+75	IL 78 / MOLINE RD.
0.04	LT. STA. 477+03 TO 480+03	IL 78 (SOUTH)	2	RT. STA. 522+25 TO 522+75	IL 78 / MOLINE RD.	0.02	RT. STA. 522+25 TO 522+75	IL 78 / MOLINE RD.
0.64	TOTAL		2	LT. STA. 555+25 TO 555+75	IL 78 / MOLINE RD.	0.02	LT. STA. 522+25 TO 522+75	IL 78 / MOLINE RD.
			2	RT. STA. 555+25 TO 555+75	IL 78 / MOLINE RD.	0.02	RT. STA. 522+25 TO 522+75	IL 78 / MOLINE RD.
			88	LT. STA. 569+75 TO 570+25	IL 78 / MOLINE RD.	0.02	LT. STA. 555+25 TO 555+75	IL 78 / MOLINE RD.
			79	RT. STA. 569+75 TO 570+25	IL 78 / MOLINE RD.	0.02	RT. STA. 555+25 TO 555+75	IL 78 / MOLINE RD.
			1	LT. STA. 417+00 TO 438+50	IL 78 (SOUTH)	0.02	LT. STA. 569+75 TO 570+25	IL 78 / MOLINE RD.
			1	RT. STA. 417+00 TO 438+50	IL 78 (SOUTH)	0.02	RT. STA. 569+75 TO 570+25	IL 78 / MOLINE RD.
			5	LT. STA. 438+50 TO 439+50	IL 78 (SOUTH)	0.98	LT. STA. 417+00 TO 438+50	IL 78 (SOUTH)
			5	RT. STA. 438+50 TO 439+50	IL 78 (SOUTH)	0.87	RT. STA. 417+00 TO 438+50	IL 78 (SOUTH)
			8	LT. STA. 439+50 TO 445+50	IL 78 (SOUTH)	0.01	RT. STA. 438+50 TO 439+50	IL 78 (SOUTH)
			18	RT. STA. 439+50 TO 445+50	IL 78 (SOUTH)	0.07	LT. STA. 439+50 TO 445+50	IL 78 (SOUTH)
			11	LT. STA. 445+50 TO 460+00	IL 78 (SOUTH)	0.06	LT. STA. 445+50 TO 460+50	IL 78 (SOUTH)
			47	RT. STA. 445+50 TO 460+00	IL 78 (SOUTH)	0.09	RT. STA. 445+50 TO 460+50	IL 78 (SOUTH)
			35	LT. STA. 475+00 TO 479+50	IL 78 (SOUTH)	0.20	LT. STA. 475+00 TO 479+50	IL 78 (SOUTH)
			58	RT. STA. 475+00 TO 479+50	IL 78 (SOUTH)	0.12	RT. STA. 475+00 TO 479+50	IL 78 (SOUTH)
			56	LT. STA. 484+00 TO 496+50	IL 78 / MOLINE RD.	2.57	TOTAL	
			59	RT. STA. 484+00 TO 496+50	IL 78 / MOLINE RD.			
			44	LT. STA. 1475+50 TO 1483+60	E. MOLINE RD.			
			52	RT. STA. 1475+50 TO 1483+60	E. MOLINE RD.			
			24	LT. STA. 50+41 TO 56+50	3RD ST.			
			11	RT. STA. 50+41 TO 56+50	3RD ST.			
			16	LT. STA. 0+50 TO 2+50	MOHAWK RD.			
			641	TOTAL				
20200100	EARTH EXCAVATION							
CU. YDS.	LOCATION	REMARK'S						
265	STA. 505+33.50 TO STA. 508+07.72	REMOVAL OF SUBGRADE (STAGE 5 & 5A)						
265	TOTAL							
20800150	TRENCH BACKFILL							
CU. YDS.	LOCATION	REMARK'S						
5.7	STA. 493+00	IL 78 / MOLINE RD.						
16.0	STA. 1482+69	E. MOLINE RD.						
21.7	TOTAL							
21101615	TOPSOIL FURNISH AND PLACE, 4"							
SQ. YDS.	LOCATION	REMARK'S						
4732	LT. STA. 417+00 TO 438+50	IL 78 (SOUTH)						
4223	RT. STA. 417+00 TO 438+50	IL 78 (SOUTH)						
70	LT. STA. 438+50 TO 439+50	IL 78 (SOUTH)						
32	RT. STA. 438+50 TO 439+50	IL 78 (SOUTH)						
320	LT. STA. 439+50 TO 445+50	IL 78 (SOUTH)						
259	RT. STA. 439+50 TO 445+50	IL 78 (SOUTH)						
275	LT. STA. 445+50 TO 460+00	IL 78 (SOUTH)						
455	RT. STA. 445+50 TO 460+00	IL 78 (SOUTH)						
949	LT. STA. 475+00 TO 479+50	IL 78 (SOUTH)						
597	RT. STA. 475+00 TO 479+50	IL 78 (SOUTH)						
2532	LT. STA. 479+50 TO 482+50	IL 78 (SOUTH)						
1888	RT. STA. 479+50 TO 482+50	IL 78 (SOUTH)						
3117	LT. STA. 484+00 TO 496+50	IL 78 / MOLINE RD.						
2990	RT. STA. 484+00 TO 496+50	IL 78 / MOLINE RD.						
3198	LT. STA. 1475+50 TO 1483+60	E. MOLINE RD.						
2357	RT. STA. 1475+50 TO 1483+60	E. MOLINE RD.						
2790	LT. STA. 50+41 TO 56+50	3RD ST.						
1299	RT. STA. 50+41 TO 56+50	3RD ST.						
584	LT. STA. 0+50 TO 2+50	MOHAWK RD.						
837	RT. STA. 0+50 TO 2+50	MOHAWK RD.						
33504	TOTAL							

FILE NAME : c:\projects\228597\228597.dgn
 LEVEL : 1
 SCALE : 1"=40'
 PLOT DATE : Thu May 13 07:11:18 2004
 OPERATOR : DUNCAN - PROGRAM DEVELOPMENT/PLANS