662847

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
71	112BR-1	IROQUOIS		3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	80% FED 20% STATE	F	BRF	F	
				CONSTRUCTION TYPE CODE				
				MAINLINE ROADWAY I000-1A	STRUCTURE X020-2A	IMPACT ATTENT. SFTY-3N		
20200100	EARTH EXCAVATION	CU YD	247	247				
20300100	CHANNEL EXCAVATION	CU YD	1072	1072				
20400800	FURNISHED EXCAVATION	CU YD	59	59				
20700220	POROUS GRANULAR EMBANKMENT	CU YD	155		155			
21300010	EXPLORATION TRENCH, SPECIAL	FOOT	1000	1000				
25000200	SEEDING, CLASS 2	ACRE	0.21	0.21				
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	19	19				
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	19	19				
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	19	19				
25100115	MULCH, METHOD 2	ACRE	0.21	0.21				
25100630	EROSION CONTROL BLANKET	SQ YD	1008.9	1008.9				
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	21	21				
28000400	PERIMETER EROSION BARRIER	FOOT	275	275				
28100107	STONE RIPRAP, CLASS A4	SQ YD	1243		1243			
28200100	FILTER FABRIC FOR USE WITH RIPRAP	SQ YD	1243		1243			
35300400	PORTLAND CEMENT CONCRETE BASE COURSE 9"	SQ YD	43.8	43.8				
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	117.9	117.9				
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	452.7	452.7				
40600300	AGGREGATE (PRIME COAT)	TON	16.4	16.4				
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	693.8	693.8				
40600990	TEMPORARY RAMP	SQ YD	60.9	60.9				
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	273.9	273.9				
42001300	PROTECTIVE COAT	SQ YD	360.3	360.3				
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	83.2	83.2				
44000100	PAVEMENT REMOVAL	SQ YD	653.6	653.6				
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	341.8	341.8				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	699	699				
44002805	ISLAND REMOVAL	SQ FT	394	394				
44004000	PAVED DITCH REMOVAL	FOOT	38	38				
44004250	PAVED SHOULDER REMOVAL	SQ YD	95.8	95.8				
48101200	AGGREGATE SHOULDERS, TYPE B	TON	32.7	32.7				

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	80% FED 20% STATE	F	BRF	F	
				CONSTRUCTION TYPE CODE				
				MAINLINE ROADWAY I000-1A	STRUCTURE X020-2A	IMPACT ATTENT. SFTY-3N		
48202600	BITUMINOUS SHOULDERS SUPERPAVE 8"	SQ YD	240.3	240.3				
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1			
50200100	STRUCTURE EXCAVATION	CU YD	265		265			
50300100	FLOOR DRAINS	EACH	14		14			
50300225	CONCRETE STRUCTURES	CU YD	157.3		157.3			
50300255	CONCRETE SUPERSTRUCTURES	CU YD	477.4		477.4			
50300260	BRIDGE DECK GROOVING	SQ YD	638		638			
50300300	PROTECTIVE COAT	SQ YD	770		770			
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	104280		104280			
51201600	FURNISHING STEEL PILES HP12X53	FOOT	1785		1785			
51202700	DRIVING STEEL PILES	FOOT	1785		1785			
51203600	TEST PILE STEEL HP12X53	EACH	4		4			
51205200	TEMPORARY SHEET PILING	SQ FT	1144		1144			
51500100	NAME PLATES	EACH	1		1			
54213453	END SECTION 18"	EACH	2	2				
542D0223	PIPE CULVERT, CLASS D, TYPE 1 18"	FOOT	10	10				
60500060	REMOVING INLETS	EACH	2	2				
60608600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	FOOT	203.8	203.8				
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	409	409				
61139900	STORM SEWERS, SPECIAL 6"	FOOT	100	100				
61140000	STORM SEWERS, SPECIAL 8"	FOOT	100	100				
61140100	STORM SEWERS, SPECIAL 10"	FOOT	100	100				
63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	162.5	162.5				
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4				
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL (TANGENT)	EACH	4	4				
63200310	GUARD RAIL REMOVAL	FOOT	561	561				
66700205	PERMANENT SURVEY MARKERS, TYPE 1	EACH	1	1				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	7	7				
67100100	MOBILIZATION	L SUM	1	1				
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1				
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1				

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SHEET 1 OF 2

SCALE: VERT. NONE HORIZ. NONE

DATE :

DRAWN BY:

CHECKED BY:

$$$$$$$$$$$$FILENAME$$$$$$$$$$$$$$
$$ $$ DATE$$ $$

...\112BQuantities\SUMMARY.dgn 07/01/2004 09:28:51 AM