ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VARIOUS	VARIOUS	MCLEAN	6	2

CONTRACT NO. 66508

GENERAL NOTES:

Plan dimensions and details relative to the existing roadway and structure have been taken from existing plans and are subject to nominal construction variations. It shall be the contractor's responsibility to verify such dimensions and details in the field and to make necessary approved adjustments prior to construction or ordering of materials. Such variations shall not be cause for additional compensation for a change in the scope of the work, however, the contractor will be paid for the quantity actually furnished at the unit price bid for the work.

The contractor shall be responsible for protecting utility property from construction operations as outlined in Article 107.31 of the Standard Specifications. The "Julie" Number is 1-800-892-0123. A minimum of forty-eight (48) hours advance notice is required.

Where section or subsection monuments are encountered, the engineer shall be notified before such monuments are removed. The contractor shall protect and carefully preserve all monuments until an authorized surveyor or agent has witnessed or otherwise referenced their location. The contractor shall be responsible for having an authorized surveyor reestablish any section of subsection monuments destroyed by his operations.

Any reference to a standard in these plans shall be interpreted to mean the edition as indicated by the subnumber listed on the index of sheets or the copy of the standard included in these plans.

The following rates of application have been used in calculation plan quantities:

Granular Materials	2.05	Tons/ Cu Yd

The existing shoulders are low. In the event that construction operations result in a drop off greater than 3" between the edge of pavement or edge of shoulder within 3' of the edge of pavement and the earth or aggregate shoulders, then the drop off shall be projected according to Article 701.04(B)(1) of the Standard Specifications. This work will be considered as included in the contract unit prices for traffic control.

DATE: _____

PREPARED BY: _____ DISTRICT OPERATIONS ENGINEER

EXAMINED BY: _____ DISTRICT CONSTRUCTION ENGINEER

_____ DISTRICT STUDIES & PLANS ENGINEER

_____ DISTRICT MATERIALS ENGINEER

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

GENERAL NOTES

JULY 13, 2004
/cmdrd5/cm508/cm508ctl1.dgn