

F&P SITE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PARK ROADS	DIST. 8 WSC 2005-2	RANDOLPH		2
STA. TO STA.				
EXISTING CONDITIONS:				
CONTRACT NO. 76803				

HIGHWAY STANDARDS

280001-02 702001-04  
542101 720001  
542301 720006  
606001-02 720011  
606301-02 729001  
780001-01

GENERAL NOTES

1. THE STANDARDS AND REVISIONS LISTED APPLY TO THIS PROJECT.
2. ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE TO BE GIVEN TO UTILITIES BEFORE DIGGING. FIELD MARKING OF FACILITIES MAY BE OBTAINED BY CONTACTING J.U.L.I.E. OR FOR NON-MEMBERS, THE UTILITY COMPANY DIRECTLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:
- ILLINOIS POWER CO.  
•EXXON MOBIL PIPELINE CO.  
•VERIZON NORTH, INC.
- (MEMBERS OF J.U.L.I.E. (800) 892-0123 ARE INDICATED BY \*. NON J.U.L.I.E. MEMBERS MUST BE NOTIFIED INDIVIDUALLY.)
3. IF SECTION OR SUB-SECTION MONUMENTS ARE ENCOUNTERED, THE ENGINEER SHALL BE NOTIFIED BEFORE SUCH MONUMENTS ARE REMOVED. THE CONTRACTOR SHALL PROTECT AND CAREFULLY PRESERVE ALL PROPERTY MARKS AND MONUMENTS UNTILL THE OWNER, AN AUTHORIZED SURVEYOR, OR AGENT HAS WITNESSED OR OTHERWISE REFERENCED THEIR LOCATION.
4. THE THICKNESS OF BITUMINOUS MIXTURES SHOWN IN THE PLANS IS THE NOMINAL THICKNESS. DEVIATIONS FROM THE NOMINAL WILL BE PERMITTED WHEN SUCH DEVIATIONS OCCUR DUE TO IRREGULARITIES IN THE EXISTING SURFACE ON WHICH THE BITUMINOIUS MIXTURE IS PLACED.
5. AN ESTIMATED 31.0 ACRES OF SEEDING CLASS 2 IS INCLUDED ON THE PLANS TO SEED ALL DISTURBED AREAS AS DIRECTED BY THE RESIDENT ENGINEER.
6. PAVEMENT MARKING FOR HANDICAPPED PARKING SHALL BE MARKED WITH YELLOW COLOR LINES AND INTERNATIONAL HANDICAPPED SYMBOLS IN ACCORDANCE WITH THE DETAIL SHOWN ON THE PLANS AND/OR AS DIRECTED BY THE ENGINEER.
7. EARTH EXCAVATION NOT SUITABLE FOR EMBANKMENT MAY BE DISPOSED OF WITHIN THE SITE AT LOCATIONS AS DIRECTED BY THE ENGINEER.
8. "ROAD CONSTRUCTION AHEAD" SIGNS SHALL BE PLACED AT THE ENTRANCE TO THE SITE WHERE WORK IS BEING CONDUCTED AND SHALL BE CLOSED TO TRAFFIC AS DIRECTED BY THE RESIDENT ENGINEER. ALL CONSTRUCTION SIGNS SHALL BE FLORESCENT ORANGE. THIS SHALL BE INCLUDED IN THE COST OF THE TRAFFIC CONTROL AND PROTECTION.
9. THE FOLLOWING MIXTURE REQUIREMENTS ARE APPLICABLE TO THIS PROJECT:
- |                                 |            |              |
|---------------------------------|------------|--------------|
| MIXTURE USES:                   | SURFACE    | LEVEL BINDER |
| AC / PC                         | PG 64-22   | PG 64-22     |
| RAP% (MAX.)                     | 15% RAP%   | 15% RAP%     |
| DESIGN AIR VOIDS:               | 4.0% @ N50 | 4.0% @ N50   |
| MIX COMPOSITION (GRADATION MIX) | IL 9.5     | IL 9.5       |
| FRICTION AGG.                   | MIXTURE C  | MIXTURE C    |
10. THE CONTRACTOR IS HEREBY ADVISED THAT FUTURE DEVELOPMENT OF THIS SITE WILL CLOSE THE HILL PRAIRIE ROAD ACCESS AT COUNTY HIGHWAY 18.

COMMITMENTS

1. THE CONTRACTOR FOR THIS CONTRACT IS ADVISED THAT OTHER PROJECTS WITHIN OR ADJACENT TO THE LIMITS OF THIS CONTRACT SECTION MAY BE UNDER CONSTRUCTION DURING CONSTRUCTION OPERATIONS FOR THIS PROJECT. THE CONTRACTOR FOR THIS SECTION SHALL COOPERATE WITH THE CONTRACTOR FOR THE OTHER PROJECTS IN ACCORDANCE WITH ARTICLE 105.08 OF THE STANDARD SPECIFICATIONS.
- IDNR - TREE AND SHRUB PLANTING CONTRACT  
IDNR - WETLAND MITIGATION CONTRACT  
IDNR - SHOOTING BERM CONTRACT  
IDOT - DIST. 8 WSC 2004-1  
CDB - WORLD SHOOTING COMPLEX CONTRACT (BUILDINGS AND SITE WORK), CONTRACT NO. 102-083-001.  
IDOT - DIST. 8 WSC 2005-1  
CITY OF SPARTA - WATER AND SANITARY SEWER UTILITY CONTRACT.
2. ALL TREE MITIGATION REQUIRED AS A RESULT OF THIS CONTRACT SHALL BE ADDRESSED BY IDNR.

FINAL  
8/17/04

ILLINOIS DEPARTMENT OF TRANSPORTATION

HIGHWAY STANDARDS, GENERAL  
NOTES AND COMMITMENTS

PARK ROADS  
SECTION DIST. 8 WSC 2005-2  
RANDOLPH COUNTY

DRAWN BY: