

CONTRACT NO. 83664




A TUCO INTERNATIONAL LTD. COMPANY


COUNTY TOTAL SHEE SECTION 96-00099-00-BR DUPAGE 62 53 TO STA, 16+55,00 STA, 13+25,00 FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT

SHEET-S22 OF S22

Contr. 83664



ANCHOR STUD DETAIL



VANE GRATE DETAIL

Notes:

All cast iron parts shall be gray iron conforming to the requirements of AASHTO M 105, Class 35B.

Bolts, anchor studs, washers and nuts shall conform to the requirements of ASTM A 307 and shall be galvanized according to AASHTO M 232.

The grate, frame and downspout shall be galvanized according to AASHTO M 111 and ASTM A 385. Downspouts located on the exterior side of a painted steel fascia beam shall be painted with the finish coat specified for the exterior side of the fascia beam.

As an alternate, bolts, anchor studs, washers and nuts may be stainless steel according to Article 1006.29(d) of the Standard Specifications.

Structural steel weldments of equal sections and of the same configuration may be substituted for cast iron. Fillet or full penetration welds shall be used for the weldments. Details shall be submitted to the Engineer for approval. The Contractor shall take appropriate measures to assure that

Protective Coat is not applied to the scupper. Cost of the Grate, Frame, Downspout, Anchor Studs, Bolts, Washers and Nuts including complete installation of the scupper shall be paid for at the contract unit price each for Drainage

BILL OF MATERIAL

Scupper, DS-12.

Drainage Scuppers, DS-12 Each 4	ITEM	UNIT	QUANTITY
	Drainage Scuppers, DS-12	Each	4

CITY OF NAPERVILLE DRAINAGE SCUPPER DS-12 DETAILS MAIN STREET BRIDGE OVER WEST BRANCH DUPAGE RIVER STRUCTURE NO. 022-6755 - STA. 15+00.00 SCALE: DRAWN BY JHR JULY 9, 2004 CHECKED BY SCD