

RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
I380	00-00083-00-PV	DuPAGE	94	7
STA.		TO STA.		
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT	

83876

FUNDING BREAKDOWN				Q23-1	Q23-2	Q23-1	Q23-2		Q23-3	07C	Q23-1	Q23-2
				80% IDOT/ 20% VILLAGE OF ADDISON	80% IDOT/ 20% VILLAGE OF ADDISON	80% IDOT/ 20% VILLAGE OF ADDISON	80% IDOT/ 20% VILLAGE OF ADDISON		80% IDOT/ 20% VILLAGE OF ADDISON	NON-PARTICIPATING/ 100% VILLAGE OF ADDISON	80% IDOT/ 20% VILLAGE OF ADDISON	80% IDOT/ 20% VILLAGE OF ADDISON
LOCATION OF WORK				FULLERTON @ LOMBARD	FULLERTON @ ADDISON	FULLERTON @ LOMBARD	FULLERTON @ ADDISON		WESTGATE TO ADDISON	PROJECT	FULLERTON @ LOMBARD	FULLERTON @ ADDISON
				CONSTRUCTION TYPE CODE 1000	ROADWAY	ROADWAY	TRAFFIC SIGNALS	TRAFFIC SIGNALS	SYSTEM INTERCONNECT	EMERGENCY PREEMPTION	HIGHWAY ILLUMINATION	HIGHWAY ILLUMINATION
CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	I000-2A	I000-2A	Y031-1F	Y031-1F		Y031-1F	Y031-3D	Y030-1E	Y030-1E
• X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	1,045								518	527
• 80400100	ELECTRIC SERVICE INSTALLATION	EACH	1								1	0
• 80700140	GROUND ROD, 5/8" DIA. X 10 FT.	EACH	32								13	19
• 80800325	TEMPORARY WOOD POLE, 45 FT., CLASS 4, 15 FT. MAST ARM	EACH	35								16	19
• 81400105	HANDHOLE (SPECIAL)	EACH	4								4	0
• 83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	290								120	170
• 83600215	LIGHT POLE FOUNDATION, 24" DIAMETER, OFFSET	FOOT	30								10	20
• 84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	32								13	19
X8950077	REMOVE AND RELOCATE EXISTING LIGHTING CONTROLLER	EACH	1								1	0
84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	1								1	0
X8040400	ELECTRIC UTILITY SERVICE CONNECTION	EACH	2								1	1
X8210450	LUMINAIRE, STREET LIGHTING, HIGH PRESSURE SODIUM VAPOR, 310 WATT, 240 VOLT	EACH	8								4	4
XX002855	TEMPORARY LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	35								16	19
XX003013	LIGHTING CONTROLLER, PAD MOUNTED, PHOTOELECTRIC CELL	EACH	1								1	0
XX004286	UNIT DUCT, WITH 3-1/C NO. 4 AND 1/C NO. 6 GROUND, 600V (XLP-TYPE RHW-2, 1 1/4" DIA., POLYETHYLENE	FOOT	6,898								3,374	3,524
XX004395	ELECTRIC CABLE IN CONDUIT, 600V (XLP) 2/C NO.10	FOOT	220								220	0

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES  
AND  
SCHEDULE OF QUANTITIES

FULLERTON AVENUE INTERSECTION IMPROVEMENTS

SCALE : NONE

DATE: 07-18-03  
DRAWN BY: SRS  
CHECKED BY: PAS