

F.A.U. ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3737	97-00072-00-FP	COOK	66	3A
STA.		TO STA.		
FED. ROAD DIST. NO. C-91-313-02		ILLINOIS	FED AID PROJECT M-8003 (235)	
CONTRACT NO. 83772				

SUMMARY OF QUANTITIES, CONTINUED			
CODE NO.	PAY ITEM	UNIT	QUANTITY
THE FOLLOWING ITEMS ARE CONSTRUCTION TYPE CODE 1000-2A			
60250400	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	1
60251500	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 11 FRAME AND GRATE	EACH	6
60251520	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 11V FRAME AND GRATE	EACH	1
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	14
** 60257600	MANHOLES TO BE ADJUSTED WITH FRAME AND GRATE (SPECIAL)	EACH	5
60261300	INLETS TO BE ADJUSTED WITH NEW TYPE 11 FRAME AND GRATE	EACH	6
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	9
60500040	REMOVING MANHOLES	EACH	7
60500050	REMOVING CATCH BASINS	EACH	7
60500060	REMOVING INLETS	EACH	3
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6, 12	FOOT	11168
** 60601005	CONCRETE CURB, TYPE B (SPECIAL)	FOOT	160
61100500	EXPLORATION TRENCH, 52" DEPTH	FOOT	152
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MD	7
67100100	MOBILIZATION	L SUM	1
** X7011005	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	L SUM	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
72000100	SIGN PANEL - TYPE 1	SQ FT	8
72900100	METAL POST - TYPE A	FOOT	20
S 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	37
S 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	9364
S 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1059
S 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	864
S 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	217

SUMMARY OF QUANTITIES, CONTINUED			
CODE NO.	PAY ITEM	UNIT	QUANTITY
THE FOLLOWING ITEMS ARE CONSTRUCTION TYPE CODE 1000-2A			
83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	7
84200700	LIGHTING FOUNDATION REMOVAL	EACH	1
84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	1
S A2001016	TREE, ACER RUBRUM (RED MAPLE), 2" CALIPER, BALLED AND BURLAPPED	EACH	8
S A2003316	TREE, FRAXINUS AMERICANA (WHITE ASH), 2" CALIPER, BALLED AND BURLAPPED	EACH	5
S A2007116	TREE, QUERCUS RUBRA (RED OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	7
S B2005616	TREE, PYRUS CALLERYANA BRADFORD (BRADFORD CALLERY PEAR), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	7
** X2800100	TEMPORARY DITCH CHECKS, ROLLED EXCELSIOR	EACH	2
** X0322035	STORM SEWER (WATER MAIN REQUIREMENTS) 18 INCH	FOOT	40
** X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	3012
** X4066614	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N50	TON	7716
** XX000714	FENCE TO BE REMOVED AND RE-ERECTED	FOOT	983
** XX001877	SUMP PUMP LINE CONNECTION	EACH	2
** Z0000990	AGGREGATE FOR TEMPORARY ACCESS	TON	222
** Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	21742
** Z0019600	DUST CONTROL WATERING	UNIT	75
Δ** Z0076600	TRAINEES	HOOR	500
** DENOTES	ITEM WITH SPECIAL PROVISION		
S DENOTES	SPECIALTY ITEM		

Δ - Y080

COPYRIGHT © 2004, BY BAXTER & WOODMAN, INC.
DESIGNED BY BAXTER & WOODMAN, INC.
DRAWN BY UKB
CHECKED BY LDH
DATE 6-08-04

CONSULTANTS	REV. NO.	DATE	DESCRIPTION
	1	8-17-04	PER I.D.O.T. AND CITY REVIEW
* REFER TO EQUIPMENT MANUFACTURER'S SHOP DRAWINGS			
30036-SUMQ.DWG UKB 25/AUG/04 15:59			



Baxter & Woodman
Crystal Lake, Illinois 815.459.1260
Burlington, Wisconsin 262.783.7834
Mokena, Illinois 708.478.8090
DeKalb, Illinois 815.787.3111
Grayslake, Illinois 847.223.5088
Rockford, Illinois 815.489.1551

CITY OF OAK FOREST, ILLINOIS
LOCKWOOD AVENUE
IMPROVEMENTS

SUMMARY OF QUANTITIES

DESIGNED BY NJP/MCU	SCALE NONE
DRAWN BY UKB	PROJECT NO. 030036
CHECKED BY LDH	SHEET NO.
DATE 6-08-04	3A OF 66