steffenmk
8 /9/2004
c:\projects\94861d\d00104pa.dgn

BROTYSCH

RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WHITE	77	20
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT NO.		

* FAI 64 (I-64)

** D-7 BRIDGE DECK REPAIRS FY 2005

CONTRACT NO. 94861

BRIDGE REPAIR SCHEDULE

	BITUMINOUS CONCRETE REMOVAL (DECK)	DECK SLAB REPAIR (PARTIAL)	DECK SLAB REPAIR (FULL DEPTH, TYPE 1)	DECK SLAB REPAIR (FULL DEPTH, TYPE 2)	BRIDGE SIDEWALK REPAIR (FULL DEPTH)	CONCRETE REMOVAL	FLOOR DRAINS	REINFORCEMENT BARS, EPOXY COATED	NEOPRENE EXPANSION JOINT 2"	NEOPRENE EXPANSION JOINT 4"	CONCRETE SUPERSTRUCTURE	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE	WATERPROOFING MEMBRANE SYSTEM	FABRIC REINFORCED ELASTOMERIC TROUGH	RELOCATING NAME PLATES	STRUCTUREAL STEEL REMOVAL	DRAINAGE SYSTEM (SPECIAL)	FURNISHING AND ERECTING STRUCTURAL STEEL	STIFFENER INTERSECTION MODIFICATION
STRUCTURE NUMBER	SQ YD	SQ YD	SQ YD	SQ YD	SQ FT	CU YD	EACH	POUND	FOOT	FOOT	CU YD	TON	SQ YD	FOOT	EACH	POUND	L. SUM	POUND	EACH
097-0003																			
W. ABUT.						5.7		1138.6		36.3	6.2				1				
PIER 4																			
PIER 8																			
PIER 12						4.9		999.2		36.3	5.6								
PIER 16						4.9		999.2		36.3	5.6								
PIER 20						4.9		999.2		36.3	5.6								
PIER 24						4.9		999.2		36.4	5.6								
E. ABUT.						5.6		834.8	36.6		5.5								
TOTAL	9018	564	5	517	1234	30.9	297	5970.2	36.6	181.6	34.1	1010	9018	64	1	1765	0.5	8325	324
097-0004																			
W. ABUT.						5.7		1138.6		36.3	6.2								
PIER 4																			
PIER 8																			
PIER 12						4.9		999.2		36.3	5.6								
PIER 16						4.9		999.2		36.3	5.6								
PIER 20						4.9		999.2		36.3	5.6								
PIER 24						4.9		999.2		36.4	5.6								
E. ABUT.						5.6		834.8	36.6		5.5				1				
TOTAL	9018	777	17	481	992	30.9	297	5970.2	36.6	181.6	34.1	1010	9018	64	1	1765	0.5	8325	324
TOTALS	18036	1341	22	998	2226	61.8	594	11940	73	363	68.2	2020	18036	128	2	3530	1.0	16650	648

FORMED CONCRETE REPAIR

STRUCTURE NUMBER	LOCATION	QUANTITY SQ FT
097-0003	EAST ABUTMENT	49.0

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

QUANTITY SCHEDULES
STR #097-0003/0004

SCALE: VERT. HORIZ.
DATE

DRAWN BY
CHECKED BY